Design

ildwood

0


PROJECT NUMBER: 1511

unless they are sealed, signed and dated.

final and ready for use, and therefor not valid,

orelimin

Copyright © 2003 by Wildwood Design Studio



(RM-4)

Limit of Construction

Plant Legend

		8				
	Sym.	Botanical Name	Common Name	*Qty.	Size	Remarks
کر	Trees	✓ EXISTING TREE	SPECIES VARIES	3	YARIES	PROTECT IN PLACE AS SHOWN ON PLAN
کر	+	RHUS LANCEA 'MULTI'	SUMAC	2	36" BOX	TALL UPRIGHT, MULTI-TRUNK (MINIMUM 120' HEIGHT, 80' WIDE, 25" CALIPER) AVAIL. THRU BASELINE TREES (602-989-9275
(($\widehat{}$	— ACACIA SALICINA	WILLOW ACACIA	5	24" BOX	TALL, UPRIGHT, WELL DEVELOPED BRANCHING STRUC (8'-0" TALL, 4'-0" WIDE, 15" MIN. CALIPER)
•		CHITALPA TASHKENTENSIS 'PINK DAWN'	PINK DAWN CHITALPA	3	24" BOX	SINGLE-TRUNK, LOW BRANCHING, VASE SHAPEI (MINIMUM 1'-0" HEIGHT, 4'-0" WIDE, 125" MIN. CALI
Sh	Ground Cover mubs & Accents	— LANTANA SP. 'NEW GOLD'	NEW GOLD LANTANA	36	1 GAL.	SPACE 3' O.C., 3' FROM HARDSCAPE
	(D) —	— DURANTA ERECTA	SKYFLOWER	49	5 GAL.	SPACE 4' O.C., 3' FROM HARDSCAPE
		TECOMA STANS	YELLOW BELLS	21	5 GAL.	SPACE 6' O.C., 5' FROM HARDSCAPE
		— CAESALPINIA PULCHERRIMA	BIRD OF PARADISE	9	5 GAL.	SPACE 6' O.C., 5' FROM HARDSCAPE
		LEUCOPHYLLUM LANGMANIA 'RIO BRAYO'	RIO BRAVO TEXAS RANGER	12	5 GAL.	SPACE 5' O.C., IN CLUSTERS AS SHOWN
	<u>(+)</u> -	TECOMA 'SPARKLETTES'	DWARF TECOMA (SPARKLETTES)	53	5 GAL.	SPACE 4' O.C., 3' FROM HARDSCAPE
	€ P —	— DASYLIRION WHEELERI	DESERT SPOON	4	5 GAL.	FULL AND BUSHY
	© —	PENSTEMON PARRYI	PARRY'S PENSTEMON	9	5 GAL.	SPACE AS SHOWN
	O -	HESPERALOE PARVIFLORA 'PERPA' BRAKELIGHTS	BRAKELIGHTS RED YUCCA	8	5 GAL.	FULL AND BUSHY

Landscape Notes:

AND LIGHT FIXTURES.

DEEMED UNACCEPTABLE.

SHOWN AWAY FROM HARDSCAPE.

CURBS, SIDEWALKS AND WALLS.

Maintenance and Guarantee

ACCEPTANCE. (PROVIDE 3 DAYS NOTICE).

AND ALL TREES FROM ACCEPTANCE DATE.

ITEMS ARE CORRECTED.

APPLICATION OF PRE-EMERGENT FOR VERIFICATION.

PLANT QUANTITIES AND DESIGN INTENT.

1. LANDSCAPE AREAS ARE DEFINED AS ALL NON-PAYED AREAS DISTURBED BY CONSTRUCTION. SLIGHT VARIATIONS MAY EXIST BETWEEN ON-SITE CONDITIONS AND 2. DRAWINGS. CONTRACTOR SHALL ADJUST PLANTING LAYOUT AS REQUIRED TO MAINTAIN

3. THE OWNER'S REPRESENTATIVE IS TO APPROVE ANY AND ALL SUBSTITUTIONS 4. LOCATE PLANTS AWAY FROM OBSTACLES SUCH AS FIRE HYDRANTS, TRANSFORMERS,

5. ALL PLANT MATERIAL SHALL MEET INDUSTRY STANDARDS. THE LANDSCAPE ARCHITECT OR

6. STAKE ALL NURSERY GROWN BOX TREES OUTSIDE ROOTBALL, SEE TREE STAKING DETAIL TREES SHALL BE A MINIMUM OF 2' FROM CURB OR SIDEWALK, SHRUBS SHALL BE 18" OR MORE AWAY FROM CURBS OR SIDEWALKS. REFER TO PLANS AND MAINTAIN SHRUB MASSING AS

7. PLANT LOCATIONS SHALL BE FLAGGED OR STAKED FOR REVIEW PRIOR TO STARTING IRRIGATION OR PLANTING EXCAVATION. MINOR RELOCATION'S SHALL BE MADE AT THIS TIME TO AVOID UNSUITABLE CONDITIONS, AT NO

8. MULCH TOPDRESSING SHALL EXTEND UNDER SHRUBS AND RAKED UNIFORMLY ALONG

9. LANDSCAPE CONTRACTOR TO CONTACT OWNER'S REPRESENTATIVE BEFORE EACH

1. LANDSCAPE CONTRACTOR SHALL NOTIFY LANDSCAPE ARCHITECT OR OWNER'S

REPRESENTATIVE FOUR (4) DAYS PRIOR TO COMPLETING IMPROVEMENTS IN ACCORDANCE WITH PLANS AND SPECIFICATIONS TO REQUEST AN INSPECTION FOR SUBSTANTIAL

COMPLETION. LANDSCAPE ARCHITECT SHALL PREPARE PUNCHLIST OF ALL WORK

REQUIRING CORRECTION. MAINTENANCE PERIOD TO BEGIN WHEN ALL PUNCHLIST

30 CALENDAR DAYS OR AS SPECIFIED BY CONTRACT, MAINTENANCE INCLUDES MOWING (WEEKLY), ADJUSTING WATER SCHEDULES, WEEDING, REMOVING DEBRIS FROM LANDSCAPE, RAKING, SPRAYING, FERTILIZING, TRIMMING, EDGING OR OTHER OPERATIONS ESSENTIAL FOR CARE, UPKEEP AND PROJECT APPEARANCE. CONTRACTOR SHALL SAND "INFILL", ROLL AND WATER SETTLE ALL LOW

3. CONTRACTOR SHALL NOTIFY ARCHITECT A MINIMUM OF ONE (1) WEEK PRIOR TO MAINTENANCE PERIOD END TO RESOLVE ANY OUTSTANDING ISSUES. A FINAL INSPECTION SHALL OCCUR TO REVIEW THE PROJECT AND ISSUE A FINAL

4. PLANTS NOT IN HEALTHY CONDITION THROUGHOUT THE WARRANTY PERIOD SHALL BE REMOVED

6. AS BUILT DRAWINGS SHALL ALSO BE PREPARED BY CONTRACTOR FOR ACTUAL

IRRIGATION LAYOUT AND SUBMITTED TO OWNER AT FINAL WALK-THROUGH. ALSO INCLUDED

IS A LAMINATED CONTROLLER SCHEDULE MOUNTED INSIDE THE BOX WITH A COPY MAILED TO THE OWNER.

TREE HEIGHTS AND CALIPERS WILL COMPLY WITH 'ARIZONA NURSERY

ASSOCIATION SPECIFICATIONS' FOR THAT TYPE AND SIZE OF TREE.

ALL LANDSCAPE MATERIAL INSTALL SHALL BE MAINTAINED BY OWNER/

LESSEE IN ACCORDANCE WITH THE APPROVED LANDSCAPE PLAN.

ALL TREES AND SHRUBS LOCATED IN THE LINE OF SIGHT WILL BE

FINISH GRADE OF LANDSCAPE AREAS (TOP OF TURF OR D.G.) MUST BE GRADED TO 1/2" BELOW CONCRETE OR OTHER PAVED SURFACE.

TREES MUST BE PLACED A MINIMUM OF 5' FROM SIDEWALKS, PUBLIC

ACCESSWAYS. SHRUBS MUST BE, AT MATURITY, 3' FROM ALL SIDES

THERE SHALL BE NO OBSTRUCTION OF SITE SIGNAGE BY LANDSCAPE

PLANT MATERIAL, AND THAT SUCH MUST BE RELOCATED/CORRECTED

BEFORE THE FIELD INSPECTION WILL ACCEPT/PASS THE SIGN IN THE

FIELD OR ISSUE A CERTIFICATE OF OCCUPANCY FOR A PROJECT

SEE CIVIL PLAN FOR ALL EXISTING AND PROPOSED UTILITY

LOCATIONS. FIELD VERIFY EXACT LOCATIONS TO AVOID ANY

FILED VERIFY EXISTING CONDITIONS AND CONTACT OWNER'S REP.

PRIOR TO COMMENCING WORK TO RESOLVE ANY POTENTIAL CONFLICTS

CONTRACTOR IS RESPONSIBLE TO REPAIR AND REPLACE ANY

CONSTRUCTION DAMAGED OR DESTROYED DURING CONSTRUCTION

EXISTING LANDSCAPE MATERIAL LOCATED OU TSIDE THE LIMIT OF

MAINTAINED FOR A CLEAR AREA BETWEEN 3' TO 1'.

OF A FIRE HYDRANT.

CONFLICTS DURING CONSTRUCTION.

AT NO ADDITIONAL COST TO THE OWNER.

AND REPLACED AT NO COST TO THE OWNER NEW PLANT MATERIAL SHALL RECEIVE THE SAME WARRANTY 5. PROVIDE ONE (1) YEAR WRITTEN GUARANTEE TO WARRANTY IRRIGATION SYSTEM

2. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING LANDSCAPE AREA FOR

SPOTS AS REQUIRED TO ACHIEVE UNIFORM GRADE WITHIN TURF AREAS.

GRADE NOTED ON LANDSCAPE PLAN TO BE FIELD VERIFIED/APPROVED BY LANDSCAPE ARCHITECT AND MODIFIED AS NECESSARY PRIOR TO ANY CONSTRUCTION REFER TO SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS NOT SHOWN ON DRAWINGS. 12. REFER TO GENERAL CONSTRUCTION NOTES (THIS SHEET) FOR ADDITIONAL CONSIDERATIONS THAT RELATE TO SCOPE OF WORK WITHIN THIS SECTION.

COORDINATE NECESSARY EXCAVATION WITH OWNERS REPRESENTATIVE.

HIS REPRESENTATIVE RESERVES THE RIGHT TO REFUSE ANY PLANT MATERIALS

'PERPA' BRAKELIGHTS YUCCA *PLANT QUANTITIES ARE FOR REFERENCE ONLY, EXACT QUANTITIES ARE THE RESPONSIBILITY OF THE CONTRACTOR.

*NOTE: ALL TREES LOCATED IN PARKING ISLANDS SHALL HAVE

A MINIMUM CANOPY CLEARANCE OF 1'-0".

Bulk Material Legend											
Sym.	Material	Common Name	Qty.	Size	Remarks						
PG -	DECOMPOSED GRANITE	EXPRESS GOLD	±12,000 SF.	3/4" SCRND.	AVAILABLE THROUGH GRANITE EXPRES (480) 354-6809. PROVIDE SAMPLE FOR FINAL						

- Key Notes: 1) 55'-0" RIGHT-OF-WAY
- 2 PROPERTY LINE

PROPOSED FINISHING CANOPY

- 4 SETBACK LINE
- [5] EXISTING CMU BLOCK WALL [6] EXISTING CONCRETE WALKWAY
- 13 EXISTING 8'-0" P.U.E. [14] EXISTING STREET RUN-OFF CATCH BASIN

8 PROPOSED CANOPY (TYP.)

[10] EXISTING 12' SEWER EASEMENT

PROVIDE 2" LAYER OF DECOMPOSED

GRANITE IN ALL PLAHTER AREAS UNLESS

OTHERWISE NOTED.

[9] EXISTING HARDSCAPE

[11] EXISTING 20'-0" PUE.

[12] EXISTING 10'-0" PUE.

(15) EXISTING HEADWALL

[16] EXISTING UTILITY BOX

[17] EXISTING EQUALIZER PIPE

[18] EXISTING COVERED PARKING

19 ADA ACCESSIBLE PARKING

(20) EXISTING MONUMENT SIGN

Granite Note:

INSTALL A 2" LAYER OF DECOMPOSED GRANITE CONTINUOUS

IN ALL PLANTERS UNDER ALL TREES AND SHRUBS. BEFORE

PLACING GRANITE, COMPACT SUB-GRADE TO 85% AND

APPLY A PRE-EMERGENT HERBICIDE TO SOIL. AFTER

PLACING GRANITE: RAKE SMOOTH, WET TO ENTIRE DEPTH,

ALLOW TO DRY, THEN LIGHTLY SCARIFY SURFACE WITH

A LEAF RAKE. APPLY A SECONDARY APPLICATION OF

PRE-EMERGENT HERBICIDE TO TOP OF GRANITE. KEEP

TOP OF GRANITE I" BELOW ADJACENT WALKS AND CURBS DO NOT ALLOW GRANITE TO TOUCH THE TRUNK OF ANY PLANT. APPLY AFTER INSTALLATION OF PLANT MATERIAL.

MESA ENGINEERING & DESIGN STANDARDS

- General Key Notes: CONTRACTOR IS RESPONSIBLE TO REMOVE ALL EXISTING TREES, SHRUBS AND GROUND COYER WITHIN THE LIMIT OF CONSTRUCTION NOT SHOWN ON THE PROJECT PLANS. PREPARE ALL LANDSCAPE
- AREAS WITHIN THE LIMIT OF CONSTRUCTION FOR NEW PLANT MATERIAL. CONTRACTOR IS RESPONSIBLE TO REMOVE ALL EXISTING GRANITE TOP DRESSING WITHIN THE LIMIT OF CONSTRUCTION NOT SHOWN ON THE PROJECT PLANS. PREPARE ALL LANDSCAPE

AREAS WITHIN THE LIMIT OF CONSTRUCTION FOR NEW GRANITE TOP DRESSING.

SITE KEY NOTE

Key Note Symbol Legend:

GENERAL KEY NOTE