

MESA DESERT UPLANDS PLANT LIST LANDSCAPE LEGEND

SALVAGED FOOTHILL PV SALVAGED FROM SITE 9- MATURE

> SALVAGED CACTUS SALVAGED FROM SITE 2-BARREL CACTUS / 16 SAGUARO

PARKINSONIA FLORIDA **BLUE PALO VERDE** 24" BOX (MATCHING)

OLNEYA TESOTA IRONWOOD

24" BOX

CHILOPSIS LINEARIS DESERT WILLOW 24" BOX

PROSOPIS VELUTINA NATIVE MESQUITE 24" BOX

CAESALPINIA CACALACO CASCALOTE 15 GALLON

> LARREA TRIDENTATA CREOSOTE BUSH 5 GALLON

DASYLIRION WHEELERII DESERT SPOON 5 GALLON

DODONEA VISCOSA HOP BUSH 5 GALLON

SIMMONSIA CHINENSIS **JOJOBA** 5 GALLON

CELTIS PALLIDA DESERT HACKBERRY 5 GALLON

NOLINA MICROCARPA BEAR GRASS 5 GALLON

ENCELIA FARINOSA BRITTLE BUSH 1 GALLON

AMBROSIA DELTOIDEA **BURR SAGE** 1 GALLON

ERICAMERIA LARCIFOLIA TERPENTINE BUSH 1 GALLON

BAILEYA MULTIRADIATA DESERT MARIGOLD 1 GALLON

SPHAERALCEA AMBIGUA DESERT GLOBE MALLOW 1 GALLON

MELAMPODIUM LEUCANTHUM BLACKFOOT DAISY 1 GALLON

> 2" MINUS (MESA DESERT UPLANDS MIX) DECOMPOSED GRANITE 2" DEPTH IN ALL LANDSCAPE AREAS

ADDITIONAL MESA NOTES:

1. REQUIRED TREES SHALL BE A MINIMUM SIZE AS SPECIFIED IN THE ARIZONA NURSERY ASSOCIATION 'RECOMMENDED TREE SPECIFICATIONS" LATEST EDITION.

2. ALL LANDSCAPE MATERIAL INSTALLED SHALL BE MAINTAINED BY THE OWNER / OR LESSEE IN ACCORDANCE WITH THE APPROVED LANDSCAPE PLAN.

REQUIRED LANDSCAPE AREAS SHALL BE FREE FROM ENCROACHMENT BY ANY USE STRUCTURE, VEHICLE OR FEATURE NOT PART OF THE LANDSCAPE DESIGN.

BACKFLOW PREVENTERS 2" OR LARGER SHALL BE SCREENED WITH LANDSCAPE MATERIALS LOCATED WITHIN A 6' RADIUS OF THE BACKFLOW PREVENTER. ALL BACKFLOW PREVENTERS LESS THAN 2" SHALL BE PLACED IN A WIRE MESH ENCLOSURE PAINTED GREEN TO DISCOURAGE THEFT AS REQUIRED BY THE POLICE DEPARTMENT

CITY OF MESA LANDSCAPE NOTES

1. ALL LANDSCAPE AREAS TO RECEIVE 2" LAYER DECOMPOSED GRANITE 2. ALL LANDSCAPE AREA TO BE WATERED BY UNDERGROUND AUTOMATIC IRRIGATION SYSTEM.

3. THE HEIGHTS AND CALIPERS SHALL COMPLY WITH 'ARIZONIA NURSERY ASSOCIATION SPECIFICATIONS' FOR THAT SIZE AND TYPE OF TREE. 4. REQUIRED TREES SHALL BE PROVIDED IN EQUAL NUMBERS OF 15 GALLON

SIZE AND 24" BOX SIZE OR LARGER. 5. REQUIRED SHRUBS SHALL HAVE A MATURE GROWTH HEIGHT OF 18" AT LEAST 50% OF REQUIRE SHRUBS SHALL BE 5 GALLON SIZE.

6.PLANT MATERIAL SHALL BE CALCULATED BASED ON A LINEAR MODULE OF 25 FEET. TREES AND SHRUBS MAY BE CLUSTERED.

ARTERIAL STREET:

(2) TREES AND (6) SHRUBS PER 25' OF STREET FRONTAGE

MAJOR, MIDSECTION COLLECTOR STREET:

(2) TREES AND (6) SHRUBS PER 25' OF STREET FRONTAGE

COLLECTOR/INDUSTRAIL/COMMERICAL STREET:

(1) TREES AND (4) SHRUBS PER 25' OF STREET FRONTAGE

PUBLIC OR PRIVATE LOCAL STREET:

(1) TREES AND (4) SHRUBS PER 25' OF STREET FRONTAGE

7. PLANT MATERIAL SIZES REQUIRED:

TREES: (TOTAL REQUIRED TREES:) 25% SHALL BE 36" BOX OR LARGER 50% SHALL BE 24" BOX OR LARGER NO TREES LESS THAN 15 GALLON

SHRUBS: (TOTAL REQUIRED SHRUBS:)

50% SHALL BE 5 GALLON OR LARGER. NO SHRUBS LESS THAN 1 GALLON

8. 1 TREES AND 3 SHRUBS FOR EVERY 15' PARKING ISLAND PARKING SHALL BE INSTALLED @ EACH END OF ROW OF STALLS AND IN BETWEEN FOR MAXIMUM OF EIGHT CONTIGUOUS PARKING SPACES 9. FOUNDATION LANDSCAPING:LANDSCAPING TO A MINIMUM HEIGHT OF 18" IS REQUIRED IMMEDIATELY ADJACENT TO, OR PROVIDED IN PLANTER AREAS ADJACENT TO BUILDING, WHICH HAVE FRONTAGE ON A PUBLIC STREET. PLANTING AREAS MUST BE A MIN. OF 5' WIDE AND A MIN. OF 50% PLANT COVERAGE.

10. THE BACKFLOW PREVENTION ASSEMBLY SHALL BE TESTED AND APPROVED BY A CERTIFIED TECHNICIAN DESIGNATED IN THE CURRENT CITY OF MESA LIST THE APPROVED INSPECTORS PRIOR TO THE REQUEST FOR FINAL INSPECTION".

11. THE REQUIRED BACKFLOW PREVENTION ASSEMBLY SHALL BE MANUFACTURER AND MODEL NUMBER DESIGNATED IN THE CURRENT CITY OF MESA LIST OF APPROVED BACKFLOW PREVENTION ASSEMBLIES".

12. ALL WORK WILL BE DONE UNDER SEPARATE PERMIT


13. ALL LANDSCAPING INSTALLED WITH THIS PROJECT TO BE MAINTAINED BY OWNERS ASSOC. OR OWNERS ASSOCIATION OF COMMERCIAL SUBDIVISION OR MANAGEMENT COMPANY IF COMMERCIAL RENTALS


14. THAT ALL TREES AND SHRUBS LOCATED IN LINE-OF-SIGHT WILL BE MAINTAINED TO A CLEAR AREA BETWEEN OF 3' TO 7'

15. RIP-RAP MUST BE ON NATURAL MATERIALS MATCHING D.G COLORS CONCRETE OR GUNITE MUST BE COLORED TO MATCH D.G. COLOR

16. TREES SHALL BE PLANTED @ LEAST 20' AWAY FROM ANY STREET LIGHT POLE OR LOCATION. SHRUBS SHALL BE PLANTED @ LEAST 7' FEET AWAY FROM ANY STREET LIGHT POLE OR LCC.

17. 10% OF TOTAL TREES IN PARKING SHALL BE 36" BOX OR LARGER.





#16222.50

SWC BROWN ROAD AND ELLSWORTH ROAD MESA, ARIZONA

8433 East Cholla St., Suite 101 Scottsdale, Arizona 85260

EMAIL: timmcqueen@timla.net

P. (602) 265-0320 F. (602) 266-6619

ASSOCIATE



MESA DESERT UPLANDS PLANT LIST LANDSCAPE LEGEND

SALVAGED FOOTHILL PV SALVAGED FROM SITE 9- MATURE

SALVAGED CACTUS
SALVAGED FROM SITE
2-BARREL CACTUS / 16 SAGUARO

2-BARREL CACTUS / 16 SAGUA
PARKINSONIA FLORIDA

PARKINSONIA FLORIDA BLUE PALO VERDE 24" BOX (MATCHING)

OLNEYA TESOTA IRONWOOD 24" BOX

CHILOPSIS LINEARIS DESERT WILLOW 24" BOX

PROSOPIS VELUTINA NATIVE MESQUITE 24" BOX

CAESALPINIA CACALACO
CASCALOTE
15 GALLON

LARREA TRIDENTATA
CREOSOTE BUSH
5 GALLON

DASYLIRION WHEELERII

DESERT SPOON

5 GALLON

DODONEA VISCOSA HOP BUSH 5 GALLON

SIMMONSIA CHINENSIS JOJOBA 5 GALLON

CELTIS PALLIDA

DESERT HACKBERRY

5 GALLON

NOLINA MICROCARPA
BEAR GRASS
5 GALLON

ENCELIA FARINOSA
BRITTLE BUSH
1 GALLON

AMBROSIA DELTOIDEA
BURR SAGE
1 GALLON

ERICAMERIA LARCIFOLIA TERPENTINE BUSH 1 GALLON

DESERT MARIGOLD

1 GALLON

SPHAERALCEA AMBIGUA

DESERT GLOBE MALLOW

1 GALLON

MELAMPODIUM LEUCANTHUM
BLACKFOOT DAISY
1 GALLON

2" MINUS (MESA DESERT UPLANDS MIX)
DECOMPOSED GRANITE
2" DEPTH IN ALL LANDSCAPE AREAS

ADDITIONAL MESA NOTES:

1. REQUIRED TREES SHALL BE A MINIMUM SIZE AS SPECIFIED IN THE ARIZONA NURSERY ASSOCIATION 'RECOMMENDED TREE SPECIFICATIONS" LATEST EDITION.

2. ALL LANDSCAPE MATERIAL INSTALLED SHALL BE MAINTAINED BY THE OWNER / OR LESSEE IN ACCORDANCE WITH THE APPROVED LANDSCAPE PLAN.

3. REQUIRED LANDSCAPE AREAS SHALL BE FREE FROM ENCROACHMENT BY ANY USE STRUCTURE, VEHICLE OR FEATURE NOT PART OF THE LANDSCAPE DESIGN.

4. BACKFLOW PREVENTERS 2" OR LARGER SHALL BE SCREENED WITH LANDSCAPE MATERIALS LOCATED WITHIN A 6' RADIUS OF THE BACKFLOW PREVENTER. ALL BACKFLOW PREVENTERS LESS THAN 2" SHALL BE PLACED IN A WIRE MESH ENCLOSURE PAINTED GREEN TO DISCOURAGE THEFT AS REQUIRED BY THE POLICE DEPARTMENT.

CITY OF MESA LANDSCAPE NOTES

1. ALL LANDSCAPE AREAS TO RECEIVE 2" LAYER DECOMPOSED GRANITE 2. ALL LANDSCAPE AREA TO BE WATERED BY UNDERGROUND AUTOMATIC IRRIGATION SYSTEM.

3. THE HEIGHTS AND CALIPERS SHALL COMPLY WITH 'ARIZONIA NURSERY ASSOCIATION SPECIFICATIONS' FOR THAT SIZE AND TYPE OF TREE.

4. REQUIRED TREES SHALL BE PROVIDED IN EQUAL NUMBERS OF 15 GALLON SIZE AND 24" BOX SIZE OR LARGER.

5. REQUIRED SHRUBS SHALL HAVE A MATURE GROWTH HEIGHT OF 18" AT LEAST 50% OF REQUIRE SHRUBS SHALL BE 5 GALLON SIZE.

6.PLANT MATERIAL SHALL BE CALCULATED BASED ON A LINEAR MODULE OF 25 FEET. TREES AND SHRUBS MAY BE CLUSTERED.

ARTERIAL STREET:

(2) TREES AND (6) SHRUBS PER 25' OF STREET FRONTAGE

MAJOR, MIDSECTION COLLECTOR STREET:

(2) TREES AND (6) SHRUBS PER 25' OF STREET FRONTAGE

COLLECTOR/INDUSTRAIL/COMMERICAL STREET:

(1) TREES AND (4) SHRUBS PER 25' OF STREET FRONTAGE PUBLIC OR PRIVATE LOCAL STREET:

(1) TREES AND (4) SHRUBS PER 25' OF STREET FRONTAGE

7. PLANT MATERIAL SIZES REQUIRED:

TREES: (TOTAL REQUIRED TREES:)

25% SHALL BE 36" BOX OR LARGER

50% SHALL BE 24" BOX OR LARGER

NO TREES LESS THAN 15 GALLON

SHRUBS: (TOTAL REQUIRED SHRUBS:)
50% SHALL BE 5 GALLON OR LARGER.
NO SHRUBS LESS THAN 1 GALLON

8. 1 TREES AND 3 SHRUBS FOR EVERY 15' PARKING ISLAND PARKING SHALL BE INSTALLED @ EACH END OF ROW OF STALLS AND IN BETWEEN FOR MAXIMUM OF EIGHT CONTIGUOUS PARKING SPACES

9. FOUNDATION LANDSCAPING:LANDSCAPING TO A MINIMUM HEIGHT OF 18" IS REQUIRED IMMEDIATELY ADJACENT TO, OR PROVIDED IN PLANTER AREAS ADJACENT TO BUILDING, WHICH HAVE FRONTAGE ON A PUBLIC STREET. PLANTING AREAS MUST BE A MIN. OF 5' WIDE AND A MIN. OF 50% PLANT COVERAGE.

10. THE BACKFLOW PREVENTION ASSEMBLY SHALL BE TESTED AND APPROVED BY A CERTIFIED TECHNICIAN DESIGNATED IN THE CURRENT CITY OF MESA LIST THE APPROVED INSPECTORS PRIOR TO THE REQUEST FOR FINAL INSPECTION".

11. THE REQUIRED BACKFLOW PREVENTION ASSEMBLY SHALL BE MANUFACTURER AND MODEL NUMBER DESIGNATED IN THE CURRENT CITY OF MESA LIST OF APPROVED BACKFLOW PREVENTION ASSEMBLIES".

12. ALL WORK WILL BE DONE UNDER SEPARATE PERMIT


13. ALL LANDSCAPING INSTALLED WITH THIS PROJECT TO BE MAINTAINED BY OWNERS ASSOC. OR OWNERS ASSOCIATION OF COMMERCIAL SUBDIVISION OR MANAGEMENT COMPANY IF COMMERCIAL RENTALS

14. THAT ALL TREES AND SHRUBS LOCATED IN LINE-OF-SIGHT WILL BE MAINTAINED TO A CLEAR AREA BETWEEN OF 3' TO 7'

15. RIP-RAP MUST BE ON NATURAL MATERIALS MATCHING D.G COLORS CONCRETE OR GUNITE MUST BE COLORED TO MATCH D.G. COLOR

16. TREES SHALL BE PLANTED @ LEAST 20' AWAY FROM ANY STREET LIGHT POLE OR LOCATION. SHRUBS SHALL BE PLANTED @ LEAST 7' FEET AWAY FROM ANY STREET LIGHT POLE OR LCC.

17. 10% OF TOTAL TREES IN PARKING SHALL BE 36" BOX OR LARGER.



PROPOSED SELF-STORAGE

SWC BROWN ROAD AND ELLSWORTH ROAD
MESA, ARIZONA
DATE: 05-15-2017 (PRELIMINARY)

© 2 0 1 6 R K A A ARCHITECTS, INC. ALL RIGHTS RESERVED. THIS DRAWING IS AN INSTRUMENT OF SERVICE. IT IS THE PROPERTY OF RKAA ARCHITECTS, INC. AND M A Y N O T BE DUPLICATED, USED OR DISCLOSED WITHOUT WRITTEN PERMISSION OF THE ARCHITECT.



McQUEEN \



