


GENERAL GRADING NOTES:

- 1. ALL GRADING AND SITE PREPARATION SHALL CONFORM WITH SPECIFICATIONS CONTAINED IN THE GEOTECHNICAL REPORT.
- 2. ALL CONSTRUCTION MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE TO THE COUNTY LATEST CONSTRUCTION SPECIFICATIONS AND DETAILS.
- 3. PRIOR TO ANY EXCAVATION OF THE PROJECT SITE, THE CONTRACTOR SHALL NOTIFY THE COUNTY 48 HOURS PRIOR TO THE START OF CONSTRUCTION.
- 4. THE CONTRACTOR SHALL CAREFULLY PRESERVE BENCHMARKS, REFERENCE POINTS AND
- 5. ALL INDICATED ELEVATIONS ARE FINISHED ELEVATIONS.
- 6. FIELD VERIFY LOCATIONS, SIZES AND IF APPLICABLE INVERTS OF EXISTING UTILITIES FOR PROPOSED CONNECTIONS PRIOR TO CONSTRUCTION.
- 7. LOCATE AND PROTECT ALL UTILITIES ASSOCIATED WITH THE PROJECT PRIOR TO CONSTRUCTION.
- 8. INSTALL SILT CONTROL MEASURES BEFORE BEGINNING SITE WORK. THESE MEASURES SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- 9. MAINTAIN PROPER SITE DRAINAGE AT ALL TIMES DURING CONSTRUCTION. PREVENT
- 10. INSTALL ALL APPROPRIATE TREE PROTECTION MEASURES PRIOR TO GRADING.
- 11. CUT AND FILL SLOPES SHALL HAVE A MAXIMUM SLOPE OF 2:1.
- 12. ALL EXCAVATION SHALL INCLUDE CLEARING, STRIPPING AND STOCKPILING TOPSOIL REMOVING UNSUITABLE MATERIALS, THE CONSTRUCTION OF EMBANKMENTS, CONSTRUCTION FILLS, AND THE FINAL SHAPING AND TRIMMING TO THE THE LINES AND GRADES SHOWN ON THE PLANS.
- 13. ALL TREES, BRUSH, AND ORGANIC TOPSOIL AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED, UNLESS OTHERWISE SPECIFIED, AND DISPOSED OF AT AN OFF-SITE LOCATION, WITH THE EXCEPTION THAT ENOUGH TOPSOIL SHALL BE RETAINED FOR RESPREAD AND GENERAL LANDSCAPING. AREAS WHICH ARE TO BE FILLED SHALL BE COMPACTED TO A MAXIMUM DENSITY OF 95% AS DETERMINED BY THE MODIFIED AASHTO COMPACTION TEST IN THE PAVED AREAS AND 85% IN THE OTHER AREAS.
- 14. STRIP AND STOCKPILE TOPSOIL. SPREAD FOUR (4) INCHES MINIMUM OF TOPSOIL ON LANDSCAPE AREAS AND REMOVE EXCESS TOPSOIL FROM SITE. PREPARE SUB-GRADE FOR PAVEMENT AND CURBS AND BACKFILL CURBS AFTER CURB CONSTRUCTION.
- 15. PROVIDE SUPPLY OF TOPSOIL FOR LANDSCAPE CONTRACTOR FOR INSTALLATION IN ALL LANDSCAPE ISLANDS.
- 16. PROVIDE AND INSTALL TOPSOIL IN DISTURBED AREAS TO BE GRASSED, TO INCLUDE PAVEMENT SHOULDERS AND DETENTION AREAS.
- 17. ALL EARTHWORK AND BASE COURSE FOR THE PARKING AREA SHALL BE COMPACTED TO A MINIMUM OF 95% MODIFIED LABORATORY DENSITY. CERTIFICATION SAID COMPACTION SHALL BE SUBMITTED BY THE CONTRACTOR TO THE ENGINEER, OR HIS/HER REPRESENTATIVE, PRIOR TO THE PLACEMENT OF THE BASE COURSE MATERIAL. BOTH PROOF ROLLING AND COMPACTION TESTING MUST BE APPROVED AND WITNESSED BY THE ENGINEER OR OWNER REPRESENTATIVE.
- 18. THE PAVEMENT SUBGRADE AND BASE COURSE MATERIAL SHALL BE INSPECTED AND APPROVED BY THE ENGINEER OR OWNER REPRESENTATIVE PRIOR TO CONSTRUCTING THE BASE AND SURFACE COURSES THEREON.
- 19. CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE TO ALL INLETS AND CATCH BASINS. AREAS OF SURFACE PONDING SHALL BE CORRECTED BY CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 20. IF AREAS ARE DISTURBED BEYOND PROPOSED GRADES BY NEGLIGENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY REGRADING OR REPAIR TO MATCH ORIGINAL EXISTING CONDITIONS.
- 21. SHORING SHALL BE DONE AS NECESSARY FOR THE PROTECTION OF THE WORK AND FOR THE SAFETY OF PERSONNEL. SHORING SHALL BE IN ACCORDANCE WITH ALL O.S.H.A AND LOCAL REGULATIONS.
- 22. STRUCTURES FOR STORM SEWERS SHALL BE IN ACCORDANCE WITH THESE IMPROVEMENT PLANS AND THE APPLICABLE STANDARD SPECIFICATIONS. WHERE GRANULAR TRENCH BACKFILL IS REQUIRED AROUND THESE STRUCTURES, THE COST SHALL BE CONSIDERED AS INCIDENTAL AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE
- 23. CONFIRM INVERTS OF ALL EXISTING STORM INLETS AND SANITARY SEWER MANHOLES BEFORE COMMENCING CONSTRUCTION.
- 24. ALL STORM SEWER LINES 18"-54" DIAMETER ARE TO BE REINFORCED CONCRETE PIPE ACCORDING TO ASTM C-76 TYPE III, UNLESS OTHERWISE SPECIFIED ON PLANS.
- 25. A GEOTEXTILE MATTING (LANDLOCK TRM 450 OR EQUIVALENT) SHALL BE USED FOR EROSION CONTROL AN ALL SLOPES GREATER THAN 3H:1V.
- 26. DRAINAGE STRUCTURES SHALL BE MAINTAINED BY PROPERTY OWNERS.
- 27. CONTRACTOR SHALL ADHERE TO PROPOSED GRADES ALONG CREEKS, ESPECIALLY IN THE AREA OF THE PROPOSED DETENTION POND. IF AREAS ARE DISTURBED BEYOND PROPOSED GRADES BY NEGLIGENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY PENALTIES INCURRED.
- 28. ALL PROPOSED SPOT ELEVATIONS SHOWN INDICATE FINISHED GRADED ELEVATIONS AT EDGE OF PAVEMENT AND/OR GRADE BREAKS, UNLESS OTHERWISE NOTED.



Know what's **below**. Call before you dig.



EXISTING LEGEND:

PROPOSED LEGEND:

PROPERTY LINE PROPOSED CURB PROPOSED CONTOUR PROPOSED DRAINAGE STRUCTURES (SEE GRADING/DRAINAGE PLANS) DRAINAGE SLOPE AND DIRECTION TOP OF SIDEWALK

XXXXX TC XXXXX G TOP OF CURB GUTTER XXXXX EX EXISTING SPOT ELEVATION

> NOTE: ALL PROPOSED SPOT ELEVATIONS HAVE A BASE ELEVATION OF 1,200 FEET

GRADING KEY NOTES

- G1A MATCH EXISTING PAVEMENT ELEVATION.
- G1B LIMITS OF SAWCUT AND PAVEMENT REMOVAL G5 0" TO 6" CURB TAPER OVER 10' REFER TO DETAIL SHEET

GreenbergFarrow 1430 W. Peachtree St. NW

Suite 200 Atlanta, GA 30309 t: 404 601 4000 f: 404 601 3970

COPYRIGHT NOTICE This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professiona


							Revisions/Submissions
			ENTITLEMENT RESUBMITTAL #2	ENGINEERING RESUBMITTAL	ENTITLEMENT RESUBMITTAL	100% SUBMISSION	
							Š.



Project No. 20191354 Scale 1:20 Drawn VICTOR LU Checked RYAN SCOTT Date 02-28-20

GRADING PLAN

C-3





GENERAL GRADING NOTES:

- 1. ALL GRADING AND SITE PREPARATION SHALL CONFORM WITH SPECIFICATIONS CONTAINED IN THE GEOTECHNICAL REPORT.
- 2. ALL CONSTRUCTION MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE TO THE COUNTY LATEST CONSTRUCTION SPECIFICATIONS AND DETAILS.
- 3. PRIOR TO ANY EXCAVATION OF THE PROJECT SITE, THE CONTRACTOR SHALL NOTIFY THE COUNTY 48 HOURS PRIOR TO THE START OF CONSTRUCTION.
- 4. THE CONTRACTOR SHALL CAREFULLY PRESERVE BENCHMARKS, REFERENCE POINTS AND
- 5. ALL INDICATED ELEVATIONS ARE FINISHED ELEVATIONS.
- 6. FIELD VERIFY LOCATIONS, SIZES AND IF APPLICABLE INVERTS OF EXISTING UTILITIES FOR PROPOSED CONNECTIONS PRIOR TO CONSTRUCTION.
- 7. LOCATE AND PROTECT ALL UTILITIES ASSOCIATED WITH THE PROJECT PRIOR TO CONSTRUCTION.
- 8. INSTALL SILT CONTROL MEASURES BEFORE BEGINNING SITE WORK. THESE MEASURES SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- 9. MAINTAIN PROPER SITE DRAINAGE AT ALL TIMES DURING CONSTRUCTION. PREVENT STORM WATER FROM RUNNING INTO OR STANDING IN EXCAVATED AREAS.
- 10. INSTALL ALL APPROPRIATE TREE PROTECTION MEASURES PRIOR TO GRADING.
- 11. CUT AND FILL SLOPES SHALL HAVE A MAXIMUM SLOPE OF 2:1.
- 12. ALL EXCAVATION SHALL INCLUDE CLEARING, STRIPPING AND STOCKPILING TOPSOIL REMOVING UNSUITABLE MATERIALS, THE CONSTRUCTION OF EMBANKMENTS, CONSTRUCTION FILLS, AND THE FINAL SHAPING AND TRIMMING TO THE THE LINES AND GRADES SHOWN ON THE PLANS.
- 13. ALL TREES, BRUSH, AND ORGANIC TOPSOIL AND OTHER OBJECTIONABLE MATERIAL SHALL BE REMOVED, UNLESS OTHERWISE SPECIFIED, AND DISPOSED OF AT AN OFF-SITE LOCATION, WITH THE EXCEPTION THAT ENOUGH TOPSOIL SHALL BE RETAINED FOR RESPREAD AND GENERAL LANDSCAPING. AREAS WHICH ARE TO BE FILLED SHALL BE COMPACTED TO A MAXIMUM DENSITY OF 95% AS DETERMINED BY THE MODIFIED AASHTO COMPACTION TEST IN THE PAVED AREAS AND 85% IN THE OTHER AREAS.
- 14. STRIP AND STOCKPILE TOPSOIL. SPREAD FOUR (4) INCHES MINIMUM OF TOPSOIL ON LANDSCAPE AREAS AND REMOVE EXCESS TOPSOIL FROM SITE. PREPARE SUB-GRADE FOR PAVEMENT AND CURBS AND BACKFILL CURBS AFTER CURB CONSTRUCTION.
- 15. PROVIDE SUPPLY OF TOPSOIL FOR LANDSCAPE CONTRACTOR FOR INSTALLATION IN ALL LANDSCAPE ISLANDS.
- 16. PROVIDE AND INSTALL TOPSOIL IN DISTURBED AREAS TO BE GRASSED, TO INCLUDE PAVEMENT SHOULDERS AND DETENTION AREAS.
- 17. ALL EARTHWORK AND BASE COURSE FOR THE PARKING AREA SHALL BE COMPACTED TO A MINIMUM OF 95% MODIFIED LABORATORY DENSITY. CERTIFICATION SAID COMPACTION SHALL BE SUBMITTED BY THE CONTRACTOR TO THE ENGINEER, OR HIS/HER REPRESENTATIVE, PRIOR TO THE PLACEMENT OF THE BASE COURSE MATERIAL. BOTH PROOF ROLLING AND COMPACTION TESTING MUST BE APPROVED AND WITNESSED BY THE ENGINEER OR OWNER REPRESENTATIVE.
- 18. THE PAVEMENT SUBGRADE AND BASE COURSE MATERIAL SHALL BE INSPECTED AND APPROVED BY THE ENGINEER OR OWNER REPRESENTATIVE PRIOR TO CONSTRUCTING THE BASE AND SURFACE COURSES THEREON.
- 19. CONTRACTOR SHALL PROVIDE POSITIVE DRAINAGE TO ALL INLETS AND CATCH BASINS. AREAS OF SURFACE PONDING SHALL BE CORRECTED BY CONTRACTOR AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 20. IF AREAS ARE DISTURBED BEYOND PROPOSED GRADES BY NEGLIGENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY REGRADING OR REPAIR TO MATCH ORIGINAL EXISTING CONDITIONS.
- 21. SHORING SHALL BE DONE AS NECESSARY FOR THE PROTECTION OF THE WORK AND FOR THE SAFETY OF PERSONNEL. SHORING SHALL BE IN ACCORDANCE WITH ALL O.S.H.A AND LOCAL REGULATIONS.
- 22. STRUCTURES FOR STORM SEWERS SHALL BE IN ACCORDANCE WITH THESE IMPROVEMENT PLANS AND THE APPLICABLE STANDARD SPECIFICATIONS. WHERE GRANULAR TRENCH BACKFILL IS REQUIRED AROUND THESE STRUCTURES, THE COST SHALL BE CONSIDERED AS INCIDENTAL AND SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR THE
- 23. CONFIRM INVERTS OF ALL EXISTING STORM INLETS AND SANITARY SEWER MANHOLES BEFORE COMMENCING CONSTRUCTION.
- 24. ALL STORM SEWER LINES 18"-54" DIAMETER ARE TO BE REINFORCED CONCRETE PIPE ACCORDING TO ASTM C-76 TYPE III, UNLESS OTHERWISE SPECIFIED ON PLANS.
- 25. A GEOTEXTILE MATTING (LANDLOCK TRM 450 OR EQUIVALENT) SHALL BE USED FOR EROSION CONTROL AN ALL SLOPES GREATER THAN 3H:1V.
- 26. DRAINAGE STRUCTURES SHALL BE MAINTAINED BY PROPERTY OWNERS.
- 27. CONTRACTOR SHALL ADHERE TO PROPOSED GRADES ALONG CREEKS, ESPECIALLY IN THE AREA OF THE PROPOSED DETENTION POND. IF AREAS ARE DISTURBED BEYOND PROPOSED GRADES BY NEGLIGENCE OF THE CONTRACTOR, THE CONTRACTOR SHALL BE
- 28. ALL PROPOSED SPOT ELEVATIONS SHOWN INDICATE FINISHED GRADED ELEVATIONS AT









EXISTING LEGEND:

	MONUMENT FOUND		POWERPOLE	—ss—	SAN. SEWER LINE	AGL	ABOVE GROUND LEVE
O	MONUMENT SET	· ····	GUY WIRE	©	SEWER MANHOLE	F.P.	FOOTPRINT
•	MAG NAIL FOUND	***	LIGHT POLE	ெ	GREASE TRAP	69	DECIDUOUS TREE
•	MAG NAIL SET	Ø0	STREET LIGHT POLE	, _{c/} O	CLEAN OUT	<u>.</u>	LANDSCAPING UNKNOWN MANHOLE
×	SET X MARK	\boxtimes	ELEC. TRANSFORMER		STORM DRAIN LINE	_	UNKNOWN MANHOLE
(R)	RECORD DATA	A/C	AIR CONDITIONER	0	STORM DRAIN MANHOLE	STOP	STOP SIGN
(M)	MEASURED DATA	O/HE	OVERHEAD ELECTRIC		STORM INLET)	CION
(C)	CALCULATED DATA	©	ELECTRIC MANHOLE	(B)	CATCH BASIN	٦	SIGN
R/W	RIGHT OF WAY	E	ELECTRIC METER			GP	GAS PEDESTAL
BSL	BACK SET LINE	EB	ELECTRIC BOX		CURB INLET	©	GAS MANHOLE
RCP	REINFORCED CONC PIPE	w_	WATER LINE	•	TELEPHONE MANHOLE -	– G –	— GAS LINE
CMP	CORRUGATED METAL PIPE	W	WATER VALVE	α_{-}	TELEPHONE POLE	G	GAS VALVE
	PLASTIC PIPE	W	WATER METER .	тр•\ — т —	TELEPHONE LINE	G	GAS METER
-c-	CABLE TELEVISION	A	HYDRANT	о/нт	OVERHEAD TELEPHONE	UG	UNDERGROUND GAS MARKER

PROPOSED LEGEND.


110103601	LOLIND.
	PROPERTY LINE
	PROPOSED CURB
XXXX	PROPOSED CONTOUR
STM->	PROPOSED HDPE STORM SEWER PIPE
\%-	DRAINAGE SLOPE AND DIRECTION
— - XXX — —	EXISTING CONTOUR



PROPOSED DRAINAGE STRUCTURES (SEE GRADING/DRAINAGE PLANS)

GRADING KEY NOTES

- G1A MATCH EXISTING PAVEMENT ELEVATION.
- G1B LIMITS OF SAWCUT AND PAVEMENT REMOVAL
- STORM SEWER (SEE NOTE FOR TYPE, SIZE AND SLOPE) STORM SEWER MANHOLE PER MAG 420 & 421 STD
- 0" TO 6" CURB TAPER OVER 10' REFER TO DETAIL SHEET
- G6 CURB INLET
- GRATE NYLOPLAST DRAIN BASIN, PER ADS STD, REFER TO C-7.5 SHEET
- WATERSTOP CONNECTION FOR HDPE TO CONCRETE STRUCTURE G14 OUTFALL STRUCTURE
- CONNECT DOWN SPOUTS UNDERGROUND TO STORM PIPE HDPE PIPE BEDDING
- REFER TO PLUMBING PLAN FOR FOUNDATION DRAIN DESIGN REFER TO PLUMBING PLAN FOR SUMP PUMP DESIGN
- G41 INSERSA TEE CONNECTION
- G42 STORM VALVE G65 UNDERGROUND DETENTION SYSTEM. REFER TO DETAILS ON C-7.5.



INST E BAS F MES

GreenbergFarrow

t: 404 601 4000 f: 404 601 3970

This drawing is the property of the above referenced Professional and is not to be used

for any purpose other than the specific

project and site named herein, and canno

be reproduced in any manner without the express written permission from the Professional

1430 W. Peachtree St. NW

Atlanta, GA 30309

Suite 200

COPYRIGHT NOTICE




Project No. 20191354 Scale 1:20 Drawn VICTOR LU Checked RYAN SCOTT


02-28-20


STORM SEWER PLAN

C-3.1



MONUMENT FOUND	Q _{WP}	POWERPOLE	—ss—	SAN. SEWER LINE		ABOVE GROUND LEV
MONUMENT SET		GUY WIRE	S	SEWER MANHOLE	F.P.	FOOTPRINT
MAG NAIL FOUND	₩	LIGHT POLE	ெ	GREASE TRAP	69	DECIDUOUS TREE
MAG NAIL SET	<i>∕</i> ~	STREET LIGHT POLE	_	CLEAN OUT	Ľ/S	LANDSCAPING
X SET X MARK	\boxtimes	ELEC. TRANSFORME	C/0	STORM DRAIN LINE	O	UNKNOWN MANHOLE
(R) RECORD DATA	A/C	AIR CONDITIONER	0	STORM DRAIN MANHOLE	STOP	STOP SIGN
(M) MEASURED DATA	O/HE	OVERHEAD ELECTRIC		STORM INLET	<u></u>	CION
(C) CALCULATED DATA	©	ELECTRIC MANHOLE	_ @	CATCH BASIN	1	SIGN
R/W RIGHT OF WAY	E	ELECTRIC METER	_		GP	GAS PEDESTAL
BSL BACK SET LINE	EB	ELECTRIC BOX		CURB INLET	©	GAS MANHOLE
RCP REINFORCED CONC PIPE	w_	- WATER LINE	•	TELEPHONE MANHOLE -	_ G _	— GAS LINE
CMP CORRUGATED METAL PIPE	W	WATER VALVE	à	TELEPHONE POLE	G	GAS VALVE
PVC PLASTIC PIPE	W)	WATER METER	TP ^C	TELEPHONE LINE	G	GAS METER
- C-CABLE TELEVISION	ā	HYDRANT	0 /UT	OVERHEAD TELEPHONE	UG	UNDERGROUND
	\sim		о/нт	OVERHEAD TELEPHONE	20	GAS MARKER






GreenbergFarrow

1430 W. Peachtree St. NW Suite 200 Atlanta, GA 30309 t: 404 601 4000 f: 404 601 3970

COPYRIGHT NOTICE This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and cannot be reproduced in any manner without the express written permission from the Professional







Project No. 20191354 Scale 1:20 Drawn VICTOR LU Checked RYAN SCOTT Date 02-28-20

PREDEVELOPED DRAINAGE PLAN

C-4





GreenbergFarrow

1430 W. Peachtree St. NW Atlanta, GA 30309 t: 404 601 4000 f: 404 601 3970

This drawing is the property of the above for any purpose other than the specific project and site named herein, and canno be reproduced in any manner without the express written permission from the Professiona

E ·	0/HE 0/HE © E E E	STREET LIGHT POLE C/O ELEC. TRANSFORMER SD AIR CONDITIONER OVERHEAD ELECTRIC ELECTRIC MANHOLE ELECTRIC METER ELECTRIC BOX WATER LINE WATER VALVE WATER METER THYDRANT O/HT	CLEAN OUT -STORM DRAIN LINE STORM DRAIN MANHOLE STORM INLET CATCH BASIN CURB INLET)/s ©	SIGN GAS PEDESTAL GAS MANHOLE		4	4	4	E
Ε	D L	EGEND:								
_	_	PROPERTY LINE					AL #2	ا ا	H.	
		PROPOSED CURB					IIT/	/TTI/	/TTI/	
		GAS LINES					RESUBMITTAL	SUBA	SUBN	
		TELEPHONE LINES						RES	RES	SION
		SANITARY SEWER LINES					VTITLEMENT	NGINEERING RESUBMITTAL	NTITLEMENT RESUBMITTAL	NOISSIMBNS %0
		WATER LINES					LEM		LEM	SUB
		UNDERGROUND ELECTR	IC LINES				 	<u>[</u>		%00

— SS — SAN. SEWER LINE AGL ABOVE GROUND LEVEL

S SEWER MANHOLE

F.P. FOOTPRINT

GENERAL UTILITY NOTES:


- 1. CONTRACTOR IS TO VERIFY THE LOCATION OF ALL EXISTING UTILITIES PRIOR TO NOTIFY ENGINEER IMMEDIATELY IF UTILITIES ARE LOCATED DIFFERENTLY THAN SHOWN. THE CONTRACTOR SHALL COORDINATE WITH EACH RESPECTIVE UTILITY COMPANY IN ORDER TO RELOCATE IF NEEDED IN CONFORMANCE WITH THEIR GUIDELINES.
- 2. CONTRACTOR SHALL NOTIFY AND COORDINATE WITH THE APPROPRIATE UTILITY COMPANY PRIOR TO THE REMOVAL OF INDICATED UTILITIES ON SITE (SEE DEMOLITION PLAN). CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ANY PERMITS REQUIRED FOR DEMOLITION AND HAUL OFF FROM THE APPROPRIATE AUTHORITIES.
- 3. AUTHORIZATION MUST BE OBTAINED FROM THE CITY OF MESA AUTHORITY TO CONSTRUCT, ALTER OR MODIFY A WATER OR SEWER LINE. CONSTRUCTION OF WATER AND SEWER INFRASTRUCTURE WILL BE AUTHORIZED BY THE WATER SYSTEM UPON: - APPROVAL OF SUBMITTED PLANS.
 - NOTIFICATION OF THE WATER SYSTEM AT LEAST 24 HOURS PRIOR TO STARTING CONSTRUCTION.
- 4. AT THE COMPLETION OF THE WATER AND/OR SEWER CONSTRUCTION AND PRIOR TO RECORDING THE FINAL PLAT, THE CONTRACTOR WILL FURNISH THE WATER SYSTEM INSPECTOR RECORD DRAWINGS OF THE PROJECT.
- 5. BUILDING CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION WITH THE GAS COMPANY FOR THE CONSTRUCTION OF THE GAS LINE BETWEEN METER AND
- 6. BUILDING CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION WITH THE POWER COMPANY FOR THE CONSTRUCTION OF ELECTRICAL CONDUIT TO PROVIDE
- 7. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING, PRIOR TO CONSTRUCTION, ALL EXISTING LOCATIONS AND INVERT ELEVATIONS OF SANITARY SEWERS, STORM DRAINAGE, AND WATER MAINS. IF ANY INVERT ELEVATION VARIES MORE THAN 0.1 FT. FROM RECORD ELEVATIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY. WORK SHALL NOT PROCEED UNTIL THE CONTRACTOR IS
- 8. CONNECT TO EXISTING UTILITIES AND INSTALL UTILITIES IN COMPLIANCE WITH REQUIREMENTS OF APPROPRIATE JURISDICTIONAL AGENCIES.
- 9. COORDINATE WITH BUILDING PLANS TO ASSURE ACCURACY OF UTILITY
- 10. ALL SEWERS TO BE MAINTAINED THROUGHOUT CONSTRUCTION, INCLUDING
- 11. ALL SURPLUS EXCAVATED MATERIAL FROM THE TRENCH SHALL BE DISPOSED OFF
- 12. COORDINATE EXACT TRENCHING, ROUTING, AND POINT OF TERMINATION WITH ALL
- 13. ALL WATER LINES SHALL HAVE AT LEAST FOUR AND ONE HALF (4.5) FEET
- ABOVE GROUND COVER FROM THE TOP OF THE PIPE TO THE FINISHED GROUND
- 14. ALL WATER LINES 2" OR SMALLER SHALL BE TYPE K-COPPER.
- 15. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING UTILITY LOCATES.

E INSTANT OIL E BASELINE R F MESA, ARIZO



Project No. 20191354 Scale 1:20 Drawn VICTOR LU Checked RYAN SCOTT Date 02-28-20

UTILITY PLAN







VALVOLINE AT 1864 E BASELINE RD

MESA, AZ

SC-310 STORMTECH CHAMBER SPECIFICATIONS

- CHAMBERS SHALL BE STORMTECH SC-310.
- CHAMBERS SHALL BE ARCH-SHAPED AND SHALL BE MANUFACTURED FROM VIRGIN, IMPACT-MODIFIED POLYPROPYLENE OR POLYETHYLENE COPOLYMERS.
- CHAMBERS SHALL MEET THE REQUIREMENTS OF ASTM F2922 (POLETHYLENE) OR ASTM F2418-16a (POLYPROPYLENE), "STANDARD SPECIFICATION FOR CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
- CHAMBER ROWS SHALL PROVIDE CONTINUOUS, UNOBSTRUCTED INTERNAL SPACE WITH NO INTERNAL SUPPORTS THAT WOULD IMPEDE FLOW OR LIMIT ACCESS FOR INSPECTION.
- THE STRUCTURAL DESIGN OF THE CHAMBERS, THE STRUCTURAL BACKFILL, AND THE INSTALLATION REQUIREMENTS SHALL ENSURE THAT THE LOAD FACTORS SPECIFIED IN THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS, SECTION 12.12, ARE MET FOR: 1) LONG-DURATION DEAD LOADS AND 2) SHORT-DURATION LIVE LOADS, BASED ON THE AASHTO DESIGN TRUCK WITH CONSIDERATION TO SECURITY OF A SHORT OF THE PROPERTY.
- FOR IMPACT AND MULTIPLE VEHICLE PRESENCES. CHAMBERS SHALL BE DESIGNED, TESTED AND ALLOWABLE LOAD CONFIGURATIONS DETERMINED IN ACCORDANCE WITH ASTM F2787
 "STANDARD PRACTICE FOR STRUCTURAL DESIGN OF THERMOPLASTIC CORRUGATED WALL STORMWATER COLLECTION CHAMBERS".
 LOAD CONFIGURATIONS SHALL INCLUDE: 1) INSTANTANEOUS (<1 MIN) ASSHTO DESIGN TRUCK LIVE LOAD ON MINIMUM COVER 2)
 MAXIMUM PERMANENT (75-YR) COVER LOAD AND 3) ALLOWABLE COVER WITH PARKED (1-WEEK) AASHTO DESIGN TRUCK.
- REQUIREMENTS FOR HANDLING AND INSTALLATION:
- TO MAINTAIN THE WIDTH OF CHAMBERS DURING SHIPPING AND HANDLING, CHAMBERS SHALL HAVE INTEGRAL, INTERLOCKING STACKING LUGS.
 TO ENSURE A SECURE JOINT DURING INSTALLATION AND BACKFILL, THE HEIGHT OF THE CHAMBER JOINT SHALL NOT BE LESS
- THAN 2".

 TO ENSURE THE INTEGRITY OF THE ARCH SHAPE DURING INSTALLATION, a) THE ARCH STIFFNESS CONSTANT AS DEFINED IN SECTION 6.2.8 OF ASTM F2922 SHALL BE GREATER THAN OR EQUAL TO 400 LBS/IN/IN. AND b) TO RESIST CHAMBER DEFORMATION DURING INSTALLATION AT ELEVATED TEMPERATURES (ABOVE 73° F / 23° C), CHAMBERS SHALL BE PRODUCED FROM REFLECTIVE GOLD OR YELLOW COLORS.
- ONLY CHAMBERS THAT ARE APPROVED BY THE SITE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE SITE DESIGN
- ONLY CHAMBERS THAT ARE APPROVED BY THE STIE DESIGN ENGINEER WILL BE ALLOWED. UPON REQUEST BY THE STIE DESIGN ENGINEER OR OWNER, THE CHAMBER MANUFACTURER SHALL SUBMIT A STRUCTURAL EVALUATION FOR APPROVAL BEFORE DELIVERING CHAMBERS TO THE PROJECT SITE AS FOLLOWS:

 THE STRUCTURAL EVALUATION SHALL BE SEALED BY A REGISTERED PROFESSIONAL ENGINEER.


 THE STRUCTURAL EVALUATION SHALL DEMONSTRATE THAT THE SAFETY FACTORS ARE GREATER THAN OR EQUAL TO 1.95 FOR DEAD LOAD AND 1.75 FOR LIVE LOAD, THE MINIMUM REQUIRED BY ASTM F2787 AND BY SECTIONS 3 AND 12.12 OF THE AASHTO LRFD BRIDGE DESIGN SPECIFICATIONS FOR THERMOPLASTIC PIPE.
- THE TEST DERIVED CREEP MODULUS AS SPECIFIED IN ASTM F2922 SHALL BE USED FOR PERMANENT DEAD LOAD DESIGN EXCEPT THAT IT SHALL BE THE 75-YEAR MODULUS USED FOR DESIGN. 9. CHAMBERS AND END CAPS SHALL BE PRODUCED AT AN ISO 9001 CERTIFIED MANUFACTURING FACILITY.


- IMPORTANT NOTES FOR THE BIDDING AND INSTALLATION OF THE SC-310 SYSTEM
- 1. STORMTECH SC-310 CHAMBERS SHALL NOT BE INSTALLED UNTIL THE MANUFACTURER'S REPRESENTATIVE HAS COMPLETED A PRE-CONSTRUCTION MEETING WITH THE INSTALLERS. 2. STORMTECH SC-310 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE" CHAMBERS ARE NOT TO BE BACKFILLED WITH A DOZER OR AN EXCAVATOR SITUATED OVER THE CHAMBERS.
- STORMTECH RECOMMENDS 3 BACKFILL METHODS:
 STONESHOOTER LOCATED OFF THE CHAMBER BED.
 BACKFILL AS ROWS ARE BUILT USING AN EXCAVATOR ON THE FOUNDATION STONE OR SUBGRADE.
 BACKFILL FROM OUTSIDE THE EXCAVATION USING A LONG BOOM HOE OR EXCAVATOR.
- THE FOUNDATION STONE SHALL BE LEVELED AND COMPACTED PRIOR TO PLACING CHAMBERS.
- JOINTS BETWEEN CHAMBERS SHALL BE PROPERLY SEATED PRIOR TO PLACING STONE.
- 6. MAINTAIN MINIMUM 6" (150 mm) SPACING BETWEEN THE CHAMBER ROWS. EMBEDMENT STONE SURROUNDING CHAMBERS MUST BE A CLEAN, CRUSHED, ANGULAR STONE 3/4-2" (20-50 mm).
- THE CONTRACTOR MUST REPORT ANY DISCREPANCIES WITH CHAMBER FOUNDATION MATERIALS BEARING CAPACITIES TO THE SITE DESIGN
- ADS RECOMMENDS THE USE OF "FLEXSTORM CATCH IT" INSERTS DURING CONSTRUCTION FOR ALL INLETS TO PROTECT THE SUBSURFACE STORMWATER MANAGEMENT SYSTEM FROM CONSTRUCTION SITE RUNOFF.
- NOTES FOR CONSTRUCTION EQUIPMENT
- STORMTECH SC-310 CHAMBERS SHALL BE INSTALLED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE". 2. THE USE OF CONSTRUCTION EQUIPMENT OVER SC-310 & SC-740 CHAMBERS IS LIMITED:
- NO EQUIPMENT IS ALLOWED ON BARE CHAMBERS.
 NO RUBBER TIRED LOADERS, DUMP TRUCKS, OR EXCAVATORS ARE ALLOWED UNTIL PROPER FILL DEPTHS ARE REACHED IN ACCORDANCE WITH THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".


 WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT CAN BE FOUND IN THE "STORMTECH SC-310/SC-740/DC-780 CONSTRUCTION GUIDE".


CONTACT STORMTECH AT 1-888-892-2694 WITH ANY QUESTIONS ON INSTALLATION REQUIREMENTS OR WEIGHT LIMITS FOR CONSTRUCTION EQUIPMENT


- FULL 36" (900 mm) OF STABILIZED COVER MATERIALS OVER THE CHAMBERS IS REQUIRED FOR DUMP TRUCK TRAVEL OR DUMPING.
- USE OF A DOZER TO PUSH EMBEDMENT STONE BETWEEN THE ROWS OF CHAMBERS MAY CAUSE DAMAGE TO THE CHAMBERS AND IS NOT AN ACCEPTABLE BACKFILL METHOD. ANY CHAMBERS DAMAGED BY THE "DUMP AND PUSH" METHOD ARE NOT COVERED UNDER THE STORMTECH STANDARD WARRANTY.
















Suite 200 Atlanta, GA 30309 t: 404 601 4000 f: 404 601 3970

COPYRIGHT NOTICE This drawing is the property of the above referenced Professional and is not to be used for any purpose other than the specific project and site named herein, and canno be reproduced in any manner without the express written permission from the Professional

1	ENTITLEMENT RESUBMITTAL #2	4/24/20
1	ENGINEERING RESUBMITTAL	4/13/20
1	ENTITLEMENT RESUBMITTAL	4/06/20
`	100% SUBMISSION	3/04/20

E BAS

68113 STEPHEN

EXPIRES: 12/31/22 Project No. 20191354 Scale N.T.S Drawn VICTOR LU Checked RYAN SCOTT

02-28-20

CONSTRUCTION DETAILS

C-7.5