

T.J. McQUEEN & ASSOCIATES, INC.

LANDSCAPE ARCHITECTURE
URBAN DESIGN
SITE PLANNING

10450 N. 74th Street, Suite 120
Scottsdale, Arizona 85258
P. (602) 265-0320

EMAIL: timmcqueen@tjmla.net


T.J. McQUEEN & ASSOCIATES, INC. LANDSCAPE ARCHITECTURE (TJMLA) EXPRESSLY RESERVES ITS COMMON LAW COPYRIGHT
& OTHER PROPERTY RIGHTS IN THESE PLANS. THESE PLANS AND ANY TO BE REPRODUCED, CHANGED OR COPIED IN
ANY FORM OR MANNER WHATSOEVER, WITHOUT THE WRITTEN PERMISSION OF TJMLA. ANY REPRODUCTION, CHANGING OR
COPYING IN ANY FORM OR MANNER WHATSOEVER, WITHOUT THE WRITTEN PERMISSION OF TJMLA, IS PROHIBITED.




Project: 19160

La01

LANDSCAPE LEGEND



CERCIDIUM 'HYBRID'
DESERT MUSEUM PALO VERDE
24" BOX



PINUS ELДАРICA
MONDEL PINE
24" BOX




CAESALPINIA CACALACO 'SMOOTHIE'
CASCALOTE
36" BOX



RUELLIA PENINSULARIS
BAJA RUELLIA
5 GALLON



TECOMA 'ORANGE JUBILEE'
ORANGE JUBILEE
5 GALLON



HESPERALOE PARVIFLORA
RED YUCCA
5 GALLON



AGAVE GEMNIFLORA
TWIN FLOWERED AGAVE
5 GALLON



LANTANA MONTEVIDENSIS
'GOLD MOUND'
1 GALLON

MATCH EXISTING R.O.W.
DECOMPOSED GRANITE
2" DEPTH IN ALL LANDSCAPE AREAS

LANDSCAPE DATA:

SITE AREA: 68,382 SQ.FT.
ON-SITE LANDSCAPE AREA: 17,229 SQ.FT. (25%)
OFF-SITE LANDSCAPE AREA: 2,729 SQ.FT.

FOUNDATION LANDSCAPE


SOUTH (80 LINEAR FEET) 80 L.F. PROVIDED (100%)
NORTH (80 LINEAR FEET) 75 L.F. PROVIDED (94%)
EAST (130 LINEAR FEET) 55 L.F. PROVIDED (42%)
WEST (130 LINEAR FEET) 112 L.F. PROVIDED (86%)

PLAZA AREA


DEPTH: 32'
AREA: 32'x30'=960 SQ.FT.

OPEN SPACE AREA


OPEN SPACE: 17,229 SQ.FT.
PLANTED OPEN SPACE: 9,820 SQ.FT. (57%)



LANDSCAPE PLAN



SOUTHERN AVE.



1. 1/2" RUBBER HOSE WITH #10 WIRE
2. TWO 2" ROUND BY 10' LONG GREEN TREE STAKES BURY 3' BELOW GRADE
3. 4" BASIN
4. GRADE (PRIOR TO GRANITE)
5. ROUGHEN SIDES OF PLANT PIT TO PREVENT GLAZING
6. AGRIFORM TABLETS
7. 2" DEPTH OF DECOMPOSED GRANITE. (SEE LEGEND FOR TYPE)

BACKFILL PLANT PIT WITH SOIL MIX PER PHX MAG SUPPLEMENT.

DOUBLE STAKING DETAIL

NOT TO SCALE

NOTE:
MULTI-TRUNKED TREES
TO HAVE ALL MAJOR
LEADERS STAKED

MULTI-TRUNK


DOUBLE-TRUNK

SINGLE-TRUNK

1. NOTCH TUBING LOOP WIRE THROUGH EXPOSED WIRE
2. #10 WIRE RUBBER COATED
3. 1/2" RUBBER HOSE

TREE GUYING DETAIL

NOT TO SCALE



1. MINIMUM DIMENSION FOR 5 GAL. PLANTS
2. 1" BASIN
3. ROUGHEN SIDES OF PLANT PIT TO PREVENT GLAZING
4. AGRIFORM TABLETS SEE SPECS. FOR RATIO
5. 2" DEPTH OF DECOMPOSED GRANITE. (SEE LEGEND FOR TYPE)

BACKFILL PLANT PIT WITH SOIL MIX PER PHX MAG SUPPLEMENT.

SHRUB PLANTING DETAIL

NOT TO SCALE