


**PLANT SCHEDULE**

SYMBOL	BOTANICAL NAME	COMMON NAME	SIZE	QTY	COMMENTS	Grass	Shrub	Tree	Other
<b>TREES</b>									
(+)	Existing Tree (To Remain)			7					
(●)	Acacia Aneura	Mulga	24" Box	7	Std Trunk Dense Canopy		x		
(○)	Cercidium praecox	Palo Brea	24" Box	24	Std Trunk Dense Canopy		x	x	x
(○)	Chilopsis linearis	Desert Willow	15 Gal	9	Multi-Trunk Dense Canopy		x	x	x
(○)	Olneya tesota	Ironwood Tree	24" Box	15	Multi-Trunk Dense Canopy		x	x	x
(○)	Olneya tesota	Ironwood Tree	36" Box	4	Multi-Trunk Dense Canopy		x	x	x
(○)	Prosopis velutina 'Rio Salado'	'Rio Salado' Native Mesquite	24" Box	14	Multi-Trunk Dense Canopy		x	x	x
<b>ACCENTS</b>									
(★)	Aloe barbadensis	Medicinal Aloe	5-Gal	46	Yellow Flower		x	x	x
(★)	Dasyliroton wheeleri	Desert Spoon	5-Gal	21	As Per Plan		x	x	x
(★)	Fouquieria splendens	Ocotillo	15-Gal	9	As Per Plan		x	x	x
(★)	Hesperaloe parviflora	Red Yucca	5-Gal	61	As Per Plan		x	x	x
<b>GRASSES</b>									
(*)	Muhlenbergia capillaris	Regal Mist Grass	5-Gal	130	As Per Plan		x	x	x
<b>SMALL SHRUBS</b>									
(○)	Ambrosia deltoidea	Bursage	5-Gal	18	As Per Plan		x	x	x
(○)	Encelia farinosa	Brittlebush	5-Gal	42	As Per Plan		x	x	x
(○)	Justicia spicigera	Mexican Honeysuckle	5-Gal	34	As Per Plan		x	x	x
(○)	Ruellia peninsularis	Baja Ruellia	5-Gal	134	As Per Plan		x	x	x
<b>TALL SHRUBS</b>									
(○)	Caesalpinia mexicana	Mexican Bird of Paradise	5-Gal	11	As Per Plan		x	x	x
(○)	Dodonaea viscosa	Hopseed Bush	5-Gal	36	As Per Plan		x	x	x
(○)	Larrea tridentata	Creosote Bush	5-Gal	15	As Per Plan		x		
(○)	Leucophyllum frutescens 'Compact'	Texas Sage	5-Gal	124	As Per Plan		x	x	
<b>GROUND COVERS</b>									
(○)	Acacia 'Desert Carpet'	Desert Carpet Acacia	1-Gal	33	As Per Plan		x	x	x
(○)	Lantana montevidensis	Purple Lantana	1-Gal	37	As Per Plan		x	x	x
(○)	Lantana 'New Gold'	'New Gold' Lantana	1-Gal	27	As Per Plan		x	x	x
<b>PERENNIAL WILDFLOWERS</b>									
(○)	Hymenoxys acaulis	Angelita Daisy	1-Gal	12	As Per Plan		x	x	x
(○)	Penstemon parryi	Parry's Penstemon	1-Gal	17	As Per Plan		x	x	x
(○)	Ruellia Brittonia 'Katie'	'Katie' Ruellia	1-Gal	13	As Per Plan		x	x	x
<b>MISCELLANEOUS</b>									
DG	Decomposed Granite - (Size: 1/2" Screened - Color: 'Desert Gold') 2" depth in all planting areas (typ)								
STABILIZED DG	Stabilized Decomposed Granite - (Size: 1/4" Minus - Color: 'Desert Gold') 3" compacted min. depth (with 1/2" x 8" deep steel plate edge on both sides of path)								
SYNTHETIC TURF	Synthetic Turf- Coronado Platinum By Arizona Artificial Lawns +/- 2,462 SF								



**hillman workshop**  
 landscape architecture  
 2901 e. highland ave  
 phoenix, az 85016  
 480-686-2001

LANDSCAPE ARCHITECT  
 AARON J. HILLMAN  
 LICENSE NO. 02.03.26  
 ARIZONA, U.S.A.  
 EXPIRES 09/30/27

**CITY OF MESA LS REQUIREMENTS**

	REQUIRED	PROVIDED
<b>RIGHT OF WAY (LONGBOW PKWY)</b> - 294 LN FT. TREES SHRUBS	1 Tree/6 Shrubs per 25 LF 12 72	7 EX & 8 NEW 74
<b>PARKING LOT ISLAND</b> TREES SHRUBS 36" BOX TREES	1 Tree/6 Shrubs per 8 Spaces 17 102 2	29 150 4
<b>HOTEL BUILDING</b> TREES 36" BOX	1 Tree per 50 LF 13 2	13 2
<b>LANDSCAPE FOR WALLS VISIBLE FROM PARKING</b>	33% OF EXTERIOR WALL	94% OF EXT. WALL
<b>OPEN SPACE AREA (NON PARKING, PERIMETER OR STREETS)</b> 21,108 SQ FT	REQUIRED 10,554 = 50%	PROVIDED 11,175 = 52.9%
<b>PLANT MATERIALS</b>		
EVERGREEN TREES	8	100 SQ FT
SHADE TREES	16	50 SQ FT
LARGE SHRUB	83	50 SQ FT
MEDIUM SHRUB	141	25 SQ FT
EVERGREEN GROUND COVER	76	25 SQ FT
<b>GRAND TOTAL</b>		11,175 SQ FT

- NOTES**
- 25% OF TREES REQUIRED IN R.O.W. SHOULD BE 36" BOX OR LARGER, WITH A MINIMUM OF 50% OF REQUIRED TREES BEING 24" BOX. NO TREES SMALLER THAN 15 GALLON.
  - 10% OF TREES REQUIRED IN PARKING ISLANDS & FOUNDATION PLANTING AREAS NEED TO BE 36" BOX WITH THE BALANCE BEING AT LEAST 24" BOX
  - 50% OF TREES REQUIRED IN PERIMETER LANDSCAPE AREAS TO BE 24" BOX WITH THE BALANCE BEING 15 GALLON.
  - 50% OF ALL REQUIRED SHRUBS TO BE 5 GALLON WITH NO SHRUBS LESS THAN 1 GALLON.
- Additional Note:  
 \*(2) ADDITIONAL 24" BOX TREES SUBSTITUTED FOR (4) 15 GALLON TREES  
 \*\* (3) 24" BOX SUBSTITUTED FOR (6) 15 GALLON TREES

- PLANT MATERIAL NOTE:**
- All plants comply with the "Longbow Business Park" Design Guidelines.
  - All plant material should conform to the Arizona Nurseryman Association standards.

- Mesa Note:**
- The landscape shall utilize a "NATURAL" maintenance program in accordance with the best management practice of the landscaping industry. 11-33-2(I)4
  - Required trees shall be minimum size as specified in the Arizona nursery association "recommended tree specifications" latest edition. 11-33-2(B)2
  - All landscape material installed shall be maintained by owner or lessee in accordance with the approved landscape plan 11-33-3(I) 2&3
  - All trees and shrubs located in the line-of-sight will be maintained for a clear area between 3'-7' and show line of sight on landscape plans.
  - required landscape areas shall be free from encroachment by any use, structure, vehicle, or feature not a part of the landscaping design 11-33-3-(A)
  - Backflow preventers 2" or larger shall be screened with landscape material located within a 6' radius of the backflow preventers (all backflow preventers less than 2" shall be placed in a wire mesh basket and painted green. (The Police Department's Crime Prevention Division has requested the change to green to discourage theft.)



DATE: 02.03.26

**Longbow Hotel and Retail Development**  
 Longbow Parkway, Mesa, Arizona

Planting Plan