

the architectural design and data contained in these documents is an instrument of service provided by FINN architects, llc.

all discrepancies found in these documents, or conflicts between these documents and actual field conditions shall be reported to FINN architects, llc. for resolution prior to commencement of the work.

discrepancies between bid amounts and these documents shall be reported to the general contractor prior to commencement of work.

notice of alternate billing cycle: this contract allows the owner to require submission of billings or estimates in billing cycles other than thirty days. a written description of such other billing cycle applicable to this project is available from the owner/owner's designated agent (see cover sheet for phone/address of owner) and the owner/designated agent shall provide this written description upon request.

december 06, 2024
schematic design
december 10, 2024
pre-application
february 06, 2025
team sp/scip/drb kickoff
february 18, 2024
design development



UTV Stereo
PERFORMANCE AUDIO
a building expansion
7561 east baseline road,
mesa, arizona

CITY OF MESA
LANDSCAPE NOTES

1. ALL LANDSCAPE AREAS TO RECEIVE 2" LAYER DECOMPOSED GRANITE
2. ALL LANDSCAPE AREA TO BE WATERED BY UNDERGROUND AUTOMATIC IRRIGATION SYSTEM.
3. THE HEIGHTS AND CALIPERS SHALL COMPLY WITH 'ARIZONIA NURSERY ASSOCIATION SPECIFICATIONS' FOR THAT SIZE AND TYPE OF TREE.
4. REQUIRED TREES SHALL BE PROVIDED IN EQUAL NUMBERS OF 15 GALLON SIZE AND 24" BOX SIZE OR LARGER.
5. REQUIRED SHRUBS SHALL HAVE A MATURE GROWTH HEIGHT OF 18" AT LEAST 50% OF REQUIRE SHRUBS SHALL BE 5 GALLON SIZE.
6. PLANT MATERIAL SHALL BE CALCULATED BASED ON A LINEAR MODULE OF 25 FEET. TREES AND SHRUBS MAY BE CLUSTERED.

- ARTERIAL STREET:
(2) TREES AND (6) SHRUBS PER 25' OF STREET FRONTAGE
- MAJOR, MIDSECTION COLLECTOR STREET:
(2) TREES AND (6) SHRUBS PER 25' OF STREET FRONTAGE
- COLLECTOR/INDUSTRIAL/COMMERCIAL STREET:
(1) TREES AND (4) SHRUBS PER 25' OF STREET FRONTAGE
- PUBLIC OR PRIVATE LOCAL STREET:
(1) TREES AND (4) SHRUBS PER 25' OF STREET FRONTAGE

7. PLANT MATERIAL SIZES REQUIRED:
- TREES: (TOTAL REQUIRED TREES:)
25% SHALL BE 36" BOX OR LARGER
50% SHALL BE 24" BOX OR LARGER
NO TREES LESS THAN 15 GALLON
- SHRUBS: (TOTAL REQUIRED SHRUBS:)
50% SHALL BE 5 GALLON OR LARGER.
NO SHRUBS LESS THAN 1 GALLON

8. 1 TREES AND 3 SHRUBS FOR EVERY 15' PARKING ISLAND
PARKING SHALL BE INSTALLED @ EACH END OF ROW OF STALLS AND IN BETWEEN FOR MAXIMUM OF EIGHT CONTIGUOUS PARKING SPACES
9. FOUNDATION LANDSCAPING: LANDSCAPING TO A MINIMUM HEIGHT OF 18" IS REQUIRED IMMEDIATELY ADJACENT TO, OR PROVIDED IN PLANTER AREAS ADJACENT TO BUILDING, WHICH HAVE FRONTAGE ON A PUBLIC STREET. PLANTING AREAS MUST BE A MIN. OF 5' WIDE AND A MIN. OF 50% PLANT COVERAGE.

10. THE BACKFLOW PREVENTION ASSEMBLY SHALL BE TESTED AND APPROVED BY A CERTIFIED TECHNICIAN DESIGNATED IN THE CURRENT CITY OF MESA LIST THE APPROVED INSPECTORS PRIOR TO THE REQUEST FOR FINAL INSPECTION".
11. THE REQUIRED BACKFLOW PREVENTION ASSEMBLY SHALL BE MANUFACTURER AND MODEL NUMBER DESIGNATED IN THE CURRENT CITY OF MESA LIST OF APPROVED BACKFLOW PREVENTION ASSEMBLIES".

12. ALL WORK WILL BE DONE UNDER SEPARATE PERMIT FOR SIGNS".

13. ALL LANDSCAPING INSTALLED WITH THIS PROJECT TO BE MAINTAINED BY OWNERS ASSOC. OR OWNERS ASSOCIATION OF COMMERCIAL SUBDIVISION OR MANAGEMENT COMPANY IF COMMERCIAL RENTALS

14. THAT ALL TREES AND SHRUBS LOCATED IN LINE-OF-SIGHT WILL BE MAINTAINED TO A CLEAR AREA BETWEEN OF 3' TO 7'

15. RIP-RAP MUST BE ON NATURAL MATERIALS MATCHING D.G COLORS CONCRETE OR GUNITIE MUST BE COLORED TO MATCH D.G. COLOR

16. TREES SHALL BE PLANTED @ LEAST 20' AWAY FROM ANY STREET LIGHT POLE OR LOCATION. SHRUBS SHALL BE PLANTED @ LEAST 7' FEET AWAY FROM ANY STREET LIGHT POLE OR LCC.

17. 10% OF TOTAL TREES IN PARKING SHALL BE 36" BOX OR LARGER.

VISIBILITY TRIANGLE INFO:

VISIBILITY TRIANGLES ARE BASED ON CITY OF MESA PUBLIC STREET ACCESS GUIDELINES DATED FEB. 15, 2005.

STREET SPEED: 45 MPH
STREET CROSS SECTION 4LU
FIGURE 2.3 (50MPH DESIGN SPEED) SD=625

ADDITIONAL NOTES:

THIS LANDSCAPE IS TO BE MAINTAINED ON A WEEKLY BASIS USING A NATURAL MAINTENANCE PROGRAM AND SHALL BE MAINTAINED IN ACCORDANCE WITH THE BEST MANAGEMENT PRACTICE OF THE LANDSCAPE INDUSTRY.

PLANT MATERIAL WITHIN THE SIGHT DISTANCE TRIANGLE SHALL NOT EXCEED 30-INCHES IN HEIGHT AT FULL MATURITY. (1105.4) TREES PLANTED WITHIN THE SIGHT DISTANCE TRIANGLES SHALL BE 24-INCH TO 42-INCH BOX SPECIMENS WITH NO BRANCHES LOWER THAN 8- FEET ABOVE THE SIDEWALK ELEVATION, AND 14- FEET OVER VEHICULAR TRAFFI WAYS.

ALL LANDSCAPE AREAS WILL BE MAINTAINED BY THIS OWNER OR LESSEE IN ACCORDANCE WITH THESE APPROVED PLANS

REQUIRED LANDSCAPE AREAS SHALL BE FREE FROM EN- CROACHMENT BY ANY USE, STRUCTURE, VEHICLE OR FEATURE NOT PART OF THE LANDSCAPE DESIGN.

BASELINE ROAD (NORTH)

PROPERTY LINE = 288'
12 TREES REQUIRED
12 TREES PROVIDED (6-36" box equiv., 6-new 36" box)
5-TREES IN THE R.O.W., 7 TREES ON-SITE
72 SHRUBS REQUIRED
72 SHRUBS PROVIDED (59 EXISTING, 13 NEW)
29 SHRUBS IN THE R.O.W., 43 SHRUBS ON-SITE

WEST PROPERTY LINE

PROPERTY LINE = 284'
12 TREES REQUIRED
12 TREES PROVIDED (12-36" box equiv.)
72 SHRUBS REQUIRED
72 SHRUBS PROVIDED (13-EXISTING, 59-NEW)

SOUTH PROPERTY LINE

PROPERTY LINE = 272'
11 TREES REQUIRED
11 TREES PROVIDED (6-36" box equiv.)
44 SHRUBS REQUIRED
44 SHRUBS PROVIDED

LANDSCAPE COVERAGE

LANDSCAPE AREA: 37,649 SQ.FT
LANDSCAPE COVERAGE REQUIRED: 18,825 SQ.FT. (50%)
LANDSCAPE COVERAGE PROVIDED: 20,707 SQ.FT. (55%)

SOSSAMAN ROAD (EAST)

PROPERTY LINE = 305'
12 TREES REQUIRED
12 TREES PROVIDED (10-36" box equiv 2-new 36" box)
2-TREES IN THE R.O.W., 10 TREES ON-SITE
72 SHRUBS REQUIRED
72 SHRUBS PROVIDED
9 SHRUBS IN THE R.O.W., 63 SHRUBS ON-SITE

PARKING LOT

PARKING STALLS = 53
12 TREES REQUIRED (3-36" box, 9-24" box)
12 TREES PROVIDED (12-36" box)
36 SHRUBS REQUIRED (5-gallon)
40 SHRUBS PROVIDED (5-gallon)

FOUNDATION BASE:

BUILDING PERIMETER: 650 L.F.T.
TREES REQUIRED: 9 TREES (2-36" BOX, 10-24" BOX)
TREES PROVIDED: 9 TREES (2-36" BOX EQUIV., 6-36" BOX)
NORTH ELEVATION: (180') 57' PROVIDED (36%)
SOUTH ELEVATION: (180') 160' PROVIDED (100%)
EAST ELEVATION: (165') 80' PROVIDED (48%)
WEST ELEVATION: (165') 45' PROVIDED (27%)

EXISTING
LANDSCAPE LEGEND

- EXISTING TREE
PROTECT FROM
CONSTRUCTION (23)
SHADE: 300 x 23 TREES = 6,900 SQ.FT OF SHADE
- EXISTING FAN PALM
PROTECT FROM
CONSTRUCTION (8)
SHADE: 131 x 8 TREES = 1,179 SQ.FT OF SHADE
- EXISTING SHRUB
PROTECT FROM
CONSTRUCTION (166)

PROPOSED
LANDSCAPE LEGEND

- PISTACHE X 'RED-PUSH'
RED PUSH PISTACHE
36" BOX (11)
SHADE: 306 x 11 TREES = 3,366 SQ.FT OF SHADE
- QUERCUS VIRGINIANA
LIVE OAK
36" BOX (18)
SHADE: 276 x 11 TREES = 3,036 SQ.FT OF SHADE
- TECOMA 'ORANGE JUBILEE'
ORANGE JUBILEE
5 GALLON (9)
- LEUCOPHYLLUM FRUTESCENS
GREEN CLOUD SAGE
5 GALLON (145)
- CAESALPINIA MEXICANA
MEXICAN BIRD OF PARADISE
5 GALLON (19)
- LANTANA MONTEVIDENSIS
'GOLD MOUND'
5 GALLON (115)

1/2" MINUS MADISON GOLD
DECOMPOSED GRANITE
2" DEPTH IN ALL LANDSCAPE AREAS

SHADE PROVIDED:
14,481 SQ.FT. OF SHADE
(16% OF TOTAL SITE)

T.J. McQUEEN & ASSOCIATES, INC.

LANDSCAPE ARCHITECTURE
URBAN DESIGN
SITE PLANNING

10446 N. 74th Street, Suite 150
Scottsdale, Arizona 85258
P.(602)265-0320

EMAIL: timmqueen@tjmla.net

