


1 Elevation 1 - a 3/8" = 1'-0"



MATERIALS & FINISH SCHEDULE:

FINISH/COLOR MATERIAL EVEREST BY DRYVIT DRYVIT W/ TERRANEO C-1 STONE FINISH CORTEN AZP RAW MTL 7.2 WESTERN RIB C-2 (PAINTED) METAL SIDING JAMES HARDIE "HARI C-3 PAINTED SHERWIN PLANK" SMOOTH LAP WILLIAMS SIDING WITH 8" SW 6258 TRICORN EXPOSURE AND 3.5" **BLACK WITH SATIN** HARDI TRIM AT **FINISH** CORNERS STEEL I-BEAM

GENERAL NOTES:

- FINISHES ARE ALSO REQUIRED AT PORTIONS OF UNDERSIDE, INSIDE FACE OF PARAPETS, AND SOFFITS EXPOSED TO PUBLIC VIEW.
- B. THE REFERENCE ELEVATION MARKED WITH REPRESENTS VERTICAL HEIGHTS RELATIVE TO INTERIOR FLOOR DATUM ASSUMED AT 100'-0", CW/CIVIL FOR ACTUAL FLOOR ELEVATION.
- ALL MATERIAL SYMBOLS ARE FOR REPRESENTATION ONLY. CONTRACTOR IS RESPONSIBLE FOR DETERMINING PROPER COURSING, ETC.
- LOCATION FOR ADDRESS SIGNAGE TO BE INSTALLED AS REQUIRED AND APPROVED BY THE CITY OF CALDWELL, ID.
- ALL ROOFTOP EQUIPMENT TO BE SCREENED BY WALLS OR EQUIPMENT SCREENS
- COORDINATE LOCATION OF KNOXBOX WITH FIRE MARSHALL.
- PROVIDE AND INSTALL SEALANT AS NEEDED AT ALL MATERIAL/SURFACE/FINISH. JOINTS TO CREATE WEATHER TIGHT SEAL. EXTERIOR CAULK COLOR TO MATCH ADJACENT MATERIAL COLOR.
- PROVIDE CONTINUOUS SEALANT AROUND ALL PENETRATIONS, ELECTRICAL LIGHTING, AND OTHER SURFACE MOUNTED COMPONENTS.

***** SHEET NOTES:

1. EVERYTHING ABOVE 12'-10" SHALL BE INSTALLED ON SITE BY FACTORY


AWNINGS TO BE INSTALLED ON SITE BY FACTORY

SCOPE DESIGNATION LEGEND

BLUE LINES AND NOTES:
 WORK TO BE PERFORMED ON SITE BY GENERAL
 CONTRACTOR (GC) AND INSPECTED IN FIELD BY LOCAL AHJ

BLACK LINES AND NOTES:
WORK TO BE PERFORMED IN FACTORY AND INSPECTED AT
FACTORY BY THIRD PARTY INSPECTION AS REQUIRED BY AHJ

GREEN LINES AND NOTES:
 WORK TO BE PERFORMED ON SITE BY FACTORY AND INSPECTED IN FIELD BY LOCAL AHJ



3BUILDING ADDRESS SIGNAGE

5210

SOO BROAD STREET
BOISE, IDAHO
THESE DRAWINGS AND SPECIFICATION INSTRUMENTS OF SERVICE, ARE AND SPECIFICATION INSTRUMENTS OF SERVICE, ARE AND SPECIFICATION INSTRUMENTS OF SERVICE AND SPECIFICATION IN STRUMENTS OF SERVICE AND SPECIFICAT

00

OUNTRY CLUB & SOUTE 50 COUNTRY CLUB DR. SHAME

PERMIT SET

PROJECT DATE
23319.009 09-20-24

DRAWN CHECKED
LMV JMO


REVISED

SHEET TITLE


EXTERIOR ELEVATIONS

SHEET

A51
ORIGINAL SHEET SIZE 24" x 36"



1 Elevation 3 - a 3/8" = 1'-0"



MATERIALS & FINISH SCHEDULE:

FINISH/COLOR MATERIAL EVEREST BY DRYVIT EFIS DRYVIT W/ TERRANEO C-1 STONE FINISH CORTEN AZP RAW MTL 7.2 WESTERN RIB C-2 (PAINTED) METAL SIDING JAMES HARDIE "HARI C-3 PAINTED SHERWIN PLANK" SMOOTH LAP WILLIAMS SIDING WITH 8" SW 6258 TRICORN EXPOSURE AND 3.5" **BLACK WITH SATIN** HARDI TRIM AT FINISH CORNERS STEEL STEEL I-BEAM

GENERAL NOTES:

- FINISHES ARE ALSO REQUIRED AT PORTIONS OF UNDERSIDE, INSIDE FACE OF PARAPETS, AND SOFFITS EXPOSED TO PUBLIC VIEW.
- THE REFERENCE ELEVATION MARKED WITH REPRESENTS VERTICAL HEIGHTS RELATIVE TO INTERIOR FLOOR DATUM ASSUMED AT 100'-0", CW/CIVIL FOR ACTUAL FLOOR ELEVATION.
- ALL MATERIAL SYMBOLS ARE FOR REPRESENTATION ONLY. CONTRACTOR IS RESPONSIBLE FOR DETERMINING PROPER COURSING, ETC.
- LOCATION FOR ADDRESS SIGNAGE TO BE INSTALLED AS REQUIRED AND APPROVED BY THE CITY OF CALDWELL, ID.
- ALL ROOFTOP EQUIPMENT TO BE SCREENED BY WALLS OR EQUIPMENT
- COORDINATE LOCATION OF KNOXBOX WITH FIRE MARSHALL.
- PROVIDE AND INSTALL SEALANT AS NEEDED AT ALL MATERIAL/SURFACE/FINISH. JOINTS TO CREATE WEATHER TIGHT SEAL. EXTERIOR CAULK COLOR TO MATCH ADJACENT MATERIAL COLOR.
- PROVIDE CONTINUOUS SEALANT AROUND ALL PENETRATIONS, ELECTRICAL LIGHTING, AND OTHER SURFACE MOUNTED COMPONENTS.

SHEET NOTES:

- EVERYTHING ABOVE 12'-10" SHALL BE INSTALLED ON SITE BY FACTORY
- AWNINGS TO BE INSTALLED ON SITE BY FACTORY
- SCUPPER AND DOWNSPOUT TO BE INSTALLED ON SITE BY FACTORY.

PERMIT SET

PROJECT 09-20-24 DRAWN CHECKED JMO

REVISED

MODULAR

5210

 ∞

SCOPE DESIGNATION LEGEND

BLUE LINES AND NOTES:
WORK TO BE PERFORMED ON SITE BY GENERAL
CONTRACTOR (GC) AND INSPECTED IN FIELD BY LOCAL AHJ

BLACK LINES AND NOTES:

WORK TO BE PERFORMED IN FACTORY AND INSPECTED AT FACTORY BY THIRD PARTY INSPECTION AS REQUIRED BY AHJ

—— GREEN LINES AND NOTES: WORK TO BE PERFORMED ON SITE BY FACTORY AND INSPECTED IN FIELD BY LOCAL AHJ

SHEET TITLE


EXTERIOR ELEVATIONS

SHEET

ORIGINAL SHEET SIZE 24" x 36"



1 NORTH ELEVATION 3/8" = 1'-0"



2EAST ELEVATION 3/8" = 1'-0"

SCHEDULE:

MATERIALS & FINISH

X	MATERIAL	#	FINIS	SH/COLOR
EFIS	DRYVIT W/ TERRANEO STONE FINISH	C-1		EVEREST BY DRYVIT
MTL	7.2 WESTERN RIB METAL SIDING	C-2		CORTEN AZP RAW (PAINTED)
HARDI	JAMES HARDIE "HARI PLANK" SMOOTH LAP SIDING WITH 8" EXPOSURE AND 3.5" HARDI TRIM AT CORNERS	C-3		PAINTED SHERWIN WILLIAMS SW 6258 TRICORN BLACK WITH SATIN FINISH
STEEL	STEEL I-BEAM			

GENERAL NOTES:

- FINISHES ARE ALSO REQUIRED AT PORTIONS OF UNDERSIDE, INSIDE FACE OF PARAPETS, AND SOFFITS EXPOSED TO PUBLIC VIEW.
- ALL MATERIAL SYMBOLS ARE FOR REPRESENTATION ONLY. CONTRACTOR IS RESPONSIBLE FOR DETERMINING PROPER COURSING, ETC.
- LOCATION FOR ADDRESS SIGNAGE TO BE INSTALLED AS REQUIRED AND APPROVED BY THE CITY OF CALDWELL, ID.
- ALL ROOFTOP EQUIPMENT TO BE SCREENED BY WALLS OR EQUIPMENT

- THE REFERENCE ELEVATION MARKED WITH REPRESENTS VERTICAL HEIGHTS RELATIVE TO INTERIOR FLOOR DATUM ASSUMED AT 100'-0", CW/CIVIL FOR ACTUAL FLOOR ELEVATION.

- COORDINATE LOCATION OF KNOXBOX WITH FIRE MARSHALL.
- PROVIDE AND INSTALL SEALANT AS NEEDED AT ALL MATERIAL/SURFACE/FINISH. JOINTS TO CREATE WEATHER TIGHT SEAL. EXTERIOR CAULK COLOR TO MATCH ADJACENT MATERIAL COLOR.
- PROVIDE CONTINUOUS SEALANT AROUND ALL PENETRATIONS, ELECTRICAL LIGHTING, AND OTHER SURFACE MOUNTED COMPONENTS.

	MA	TERIAL CAI	LCULATI	ON						
	WEST		SOUTH		EAST		NORTH		TOTAL	
MATERIAL		%	SF	%	SF	%	SF	%	SF	%
TOTAL ELEVATION AREA		100%	872	100%	325	100%	872	100%	2394	100%
GLAZED DOORS AND WINDOWS		0.0%	0	0.0%	46	14.2%	68	7.8%	114	4.8%
NON-GLAZED DOORS AND WINDOWS		0.0%	69	7.9%	0	0.0%	25	2.9%	94	3.9%
TOTAL (GLAZED/NON-GLAZED DOORS AND WINDOWS)		0.0%	69	7.9%	46	14.2%	93	10.7%	208	8.7%
EIFS (C-1 EVEREST)		0.0%	0	0.0%	74	22.8%	346	39.7%	420	17.5%
WESTERN RIB (C-2 CORTEN AZP RAW)		68.6%	398	45.6%	182	56.0%	368	42.2%	1171	48.9%
JAMES HARDIE LAP SIDING(C-3 BLACK)		23.4%	348	39.9%	0	0.0%	0	0.0%	424	17.7%
TOTAL (WALL MATERIALS)		92.0%	746	85.6%	256	78.8%	714	81.9%	2015	84.2%
PAINTED METAL TRIM (WHITE)		0.0%	0	0.0%	3	0.9%	23	2.6%	26	1.1%
PAINTED METAL TRIM (BROWN)		3.7%	15	1.7%	10	3.1%	14	1.6%	51	2.1%
PAINTED METAL TRIM (BLACK)		4.3%	42	4.8%	10	3.1%	28	3.2%	94	3.9%
TOTAL (PAINTED METAL TRIM)		8.0%	57	6 50%	23	7 1%	65	7 5%	171	7 1%

 ∞


PERMIT SET

09-20-24 CHECKED DRAWN


REVISED

RENDERED **ELEVATIONS**

ORIGINAL SHEET SIZE 24" x 36"



1 SOUTH ELEVATION 3/8" = 1'-0"



MATERIAL CALCULATION										
	WEST		SOUTH		EAST		NORTH		TOTAL	
MATERIAL		%	SF	%	SF	%	SF	%	SF	%
TOTAL ELEVATION AREA	325	100%	872	100%	325	100%	872	100%	2394	100%
GLAZED DOORS AND WINDOWS		0.0%	0	0.0%	46	14.2%	68	7.8%	114	4.8%
NON-GLAZED DOORS AND WINDOWS	0	0.0%	69	7.9%	0	0.0%	25	2.9%	94	3.9%
TOTAL (GLAZED/NON-GLAZED DOORS AND WINDOWS)	0	0.0%	69	7.9%	46	14.2%	93	10.7%	208	8.7%
EIFS (C-1 EVEREST)	0	0.0%	0	0.0%	74	22.8%	346	39.7%	420	17.5%
WESTERN RIB (C-2 CORTEN AZP RAW)	223	68.6%	398	45.6%	182	56.0%	368	42.2%	1171	48.9%
JAMES HARDIE LAP SIDING(C-3 BLACK)	76	23.4%	348	39.9%	0	0.0%	0	0.0%	424	17.7%
TOTAL (WALL MATERIALS)	299	92.0%	746	85.6%	256	78.8%	714	81.9%	2015	84.2%
PAINTED METAL TRIM (WHITE)	0	0.0%	0	0.0%	3	0.9%	23	2.6%	26	1.1%
PAINTED METAL TRIM (BROWN)	12	3.7%	15	1.7%	10	3.1%	14	1.6%	51	2.1%
PAINTED METAL TRIM (BLACK)		4.3%	42	4.8%	10	3.1%	28	3.2%	94	3.9%
TOTAL (PAINTED METAL TRIM)		8.0%	57	6.5%	23	7.1%	65	7.5%	171	7.1%

MATERIALS & FINISH SCHEDULE:

X	MATERIAL	#	FINIS	H/COLOR
	DRYVIT W/ TERRANEO STONE FINISH	C-1		EVEREST BY DRYVIT
	7.2 WESTERN RIB METAL SIDING	C-2		CORTEN AZP RAW (PAINTED)
	JAMES HARDIE "HARI PLANK" SMOOTH LAP SIDING WITH 8" EXPOSURE AND 3.5" HARDI TRIM AT CORNERS STEEL I-BEAM	C-3		PAINTED SHERWIN WILLIAMS SW 6258 TRICORN BLACK WITH SATIN FINISH

GENERAL NOTES:

- A. FINISHES ARE ALSO REQUIRED AT PORTIONS OF UNDERSIDE, INSIDE FACE OF PARAPETS, AND SOFFITS EXPOSED TO PUBLIC VIEW.
- B. THE REFERENCE ELEVATION MARKED WITH REPRESENTS VERTICAL HEIGHTS RELATIVE TO INTERIOR FLOOR DATUM ASSUMED AT 100'-0", CW/CIVIL FOR ACTUAL FLOOR ELEVATION.
- C. ALL MATERIAL SYMBOLS ARE FOR REPRESENTATION ONLY. CONTRACTOR IS RESPONSIBLE FOR DETERMINING PROPER COURSING, ETC.
- D. LOCATION FOR ADDRESS SIGNAGE TO BE INSTALLED AS REQUIRED AND APPROVED BY THE CITY OF CALDWELL, ID.
- E. ALL ROOFTOP EQUIPMENT TO BE SCREENED BY WALLS OR EQUIPMENT SCREENS
- F. COORDINATE LOCATION OF KNOXBOX WITH FIRE MARSHALL.
- PROVIDE AND INSTALL SEALANT AS NEEDED AT ALL MATERIAL/SURFACE/FINISH. JOINTS TO CREATE WEATHER TIGHT SEAL. EXTERIOR CAULK COLOR TO MATCH ADJACENT MATERIAL COLOR.
- PROVIDE CONTINUOUS SEALANT AROUND ALL PENETRATIONS, ELECTRICAL LIGHTING, AND OTHER SURFACE MOUNTED COMPONENTS.

BLACK ROCK COI COUNTRY CLUB & SOI 1050 COUNTRY CLUB D

85210

PERMIT SET

ROJECT	DATE				
INOULUI	DATE				
23319.009	09-20-24				
	00 _0				
RAWN	CHECKED				
TAVVIN	CHECKED				
LMV	JMO				
LIVI V	01110				
	·				


REVISED

RENDERED ELEVATIONS

SHEET

A54
ORIGINAL SHEET SIZE 24" x 36"

2WEST ELEVATION
3/8" = 1'-0"











PERMIT SET

09-20-24

CHECKED

JMO

PROJECT

DRAWN

LMV

REVISED

SHEET TITLE

SHEET

RENDERINGS

ORIGINAL SHEET SIZE 24" x 36"