

## PLANTING NOTES


- 1. The Contractor must verify the location and depth of all existing and proposed underground utilities and facilities prior to beginning construction activities, as per Act 38, call 1-800-242-1776.
- 2. The Contractor shall stake out the location of all proposed plant material for review by the Owner's Representative prior to installation.
- 3. The Contractor shall not deviate from the proposed Plant Schedule without written approval by the Owner's Representative.
- 4. All plant material shall be in accordance with the American Standard for Nursery Stock, latest edition.
- 5. Substitutions: When plants of a specified type or size are not available within a reasonable distance, substitutions may be made upon request by the Contractor, if approved by the Owner's Representative. The Contractor shall notify the Owner's Representative in writing of any plant material which will not be available, prior to submitting a bid on this project. If a bid is received without such qualification, it will be assumed no such substitution will be proposed.
- 6. Plants with broken root balls or excessive damage to the crown will be replaced at no charge to the Owner prior to installation.
- 7. Trees in leaf when planted shall be treated with anti-desiccant such as Wiltproof (or an occupational equivalent approved by the Owner's Representative).
- 8. Preparation of planting soil: before mixing, clean topsoil of roots, vegetation, stones, clay lumps, and other extraneous materials harmful to plant growth. Planting soil for trees shall be amended as directed by the soil test results completed by the Contractor. Provide a copy of the soil test results to the Owner's Representative.
- 9. The Contractor is responsible for any adjustments to soil pH, fertility, and/or drainage conditions necessary to ensure proper growing conditions for proposed plantings. Proposed solution to be presented to and approved by the Owner's Representative prior to execution.
- 10. Field conditions may dictate minor adjustments to the location of plant material. Before adjustments of plant locations occur, the Contractor shall notify the Owner's Representative.
- 11. Contractor to give 48 hour notice to Owner's Representative before planting occurs, so Owner's Representative can approve layout of plants.
- 12. Quantities in Plant Schedule to overrider quantities shown on Site Landscape Plan.
- 13. Trees shall be installed no less than 3' from back of curb.


## Planting Schedule

SAIA Mesa, Arizona

CODE	SCIENTIFIC NAME	COMMON NAME	SIZE	QUANTITY	SPACING
TREES	& SHRUBS				
PF	Parkinsonia florida	Blue Palo Verde	36-Inch Box	35	As shown
PV	Prosopis velutina	Velvet Mesquite	24-Inch Box	55	As shown
ОТ	Olneya tesota	Desert Ironwood	24-Inch Box	23	As shown
LF	Leucophyllum frutescens	Texas Sage	5 GAL	119	As shown

CACTI & SUCCULENTS					
CG	Carnegiea gigantea	Saguaro	15 GAL	11	As shown
НР	Hesperaloe parviflora	Red Yucca	5 GAL / TOS	179	As shown
OS	Opuntia santa-rita	Santa Rita Prickly Pear	5 GAL / TOS	20	As shown
YE	Yucca elata	Soaptree yucca	5 GAL / TOS	44	As shown






SHRUB PLANTING: 1 & 5 GALLON PLANTS

ĽH.F. LENZ ENGINEERING AZ #: 13460-0 **Headquarters:** 1407 Scalp Avenue Johnstown, PA 15904 814-269-9300 www.hflenz.com

**environmental** planning & design uc 100 ross street, suite 500 pittsburgh, pa 15219 www.epd-pgh.com 412.261.6000



Project Identification:

SAIA MOTOR FREIGHT LINE, LLC PROPOSED TRUCKING FREIGHT FACILITY E PECOS ROAD, CITY OF MESA, MARICOPA COUNTY, ARIZONA

No.:	Date:	Description:

Sheet Title: LANDSCAPE

**DETAILS & NOTES** 

2022-0602.01 Project No.: Cadd File: Drawn By: JDS Checked By: 03/29/2024 Copyright: C 2023 H.F. LENZ COMPANY