



Date: 8/22/2016

Filename: G:\Cad Projects\1402-16-Longbow\PHOTOMETRICS\1402-16-2.AGI

Calculation Summary

Label	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
ENTIRE SITE	Illuminance	Fc	2.58	11.9	0.1	25.80	119.00
SPILL @ PROPERTY LINE	Illuminance	Fc	0.04	0.3	0.0	N.A.	N.A.

Luminaire Schedule

Symbol	Qty	Label	Arrangement	Total Lamp Lumens	LLF	Description
[Symbol]	3	P1	SINGLE	N.A.	0.950	NLS-VUE-1-T5-32L-700-40K-SINGLE @ 12' MTG. HT.
[Symbol]	5	S1A	SINGLE	N.A.	0.950	NLS-VUE-1-T4-48L-1050-40K-SINGLE @ 25' MTG. HT. WHSS
[Symbol]	8	S1B	SINGLE	N.A.	0.950	NLS-VUE-1-T2-48L-1050-40K-SINGLE @ 25' MTG. HT.
[Symbol]	3	S1C	SINGLE	N.A.	0.950	NLS-VUE-1-T2-48L-1050-40K-SINGLE @ 25' MTG. HT.
[Symbol]	1	S1D	SINGLE	N.A.	0.950	NLS-VUE-1-T2-32L-700-40K-SINGLE @ 20' MTG. HT. WHSS
[Symbol]	12	S2C	BACK-BACK	N.A.	0.950	NLS-VUE-1-T5-64L-1050-55K-SINGLE @ 25' MTG. HT.
[Symbol]	2	WM	SINGLE	N.A.	0.950	NLS-VUE-1-T5-64L-1050-55K-TWIN @ 25' MTG. HT.
[Symbol]	2	WM-1	SINGLE	N.A.	1.000	NLS-VUE-1-T4-48L-1050-40K-WALL MT @ 25' MTG. HT.

RECKER ROAD

LONGBOW PARKWAY