
SOUTH E	ELEVATION - 717 SQ. FT.		
SYMBOL	MATERIAL	SQ. FT.	PERCENT
A	CONCRETE	52	7.30%
В	VERTICAL WOOD PLANK	351	49.00%
С	STUCCO	21	3.00%
E/F	METAL CANOPIES & FLASHING	91	12.70%
J	SPLIT-FACED CMU WAINSCOT	102	14.20%
	STOREFRONT GARAGE DOOR	99	13.80%



WEST EL	EVATION - 1,426 SQ. FT.		
SYMBOL	MATERIAL	SQ. FT.	PERCENT
A	CONCRETE	263	18.4%
В	VERTICAL WOOD PLANK	143	10.0%
C	STUCCO	391	27.5%
E/F	METAL CANOPIES & FLASHING	172	12.0%
G	LOUVERS	245	17.2%
J	SPLIT-FACED CMU WAINSCOT	212	14.9%

SOUTH ELEVATION - FRONT

SCALE: 1/4"=1'-0"

ALL ROOF MOUNTED MECHANICAL UNITS ARE TO BE FULLY SCREENED BY THE BUILDING



WEST ELEVATION - OUTSIDE DRIVE-THRU

SCALE: 1/4"=1'-0"

KEYED NOTES (APPLIES TO SHEETS A6.0 & A6.1)

- S.E.S. CLOSET DOORS TO HAVE SIGNAGE AS REQUIRED BY THE ELECTRIC SERVICE.
- FIRE RISER ROOM DOOR TO HAVE SIGNAGE AS
- REQUIRED BY THE FIRE DEPARTMENT.
- SPEAKER ORDER STAND W/ CREDIT CARD READER AND WEATHER SHIELD.
- EXTERIOR RATED WALK-IN COOLER PANEL & DOOR WITH BLACK FACTORY FINISH.
- DELIVERY DOOR BELL BUTTON AT +48" A.F.F. AT REAR SERVICE DOOR.
- EXTERIOR WALL MOUNTED AIR CURTAIN, RECESSED INTO METAL CANOPY. REFER TO MECHANICAL DRAWINGS.
- EXTERIOR WALL MOUNTED AIR CURTAIN, RECESSED INTO TOWER WALL ABOVE DRIVE-THRU WINDOW. REFER TO MECHANICAL DRAWINGS.
- DRIVE-THRU WINDOW RECESSED INTO TOWER, SILL TO BE CLAD WITH 16 GA. S/S WITH 2" EDGE TURN DOWN.
- DASHED LINE INDICATES OUTLINE OF ROOFTOP EQUIPMENT.
- 10. LINE OF ROOF DECK, SHOWN DASHED.
- 11. EXTERIOR LIGHTING, REFER TO ELECTRICAL DRAWINGS.
- 12. HOSE BIBB, REFER TO PLUMBING DRAWINGS.
- 13. BOLLARD W/ 2" REFLECTIVE YELLOW TAPE AT TOP
- 14. 12" TALL BLACK HELVETICA BUILDING ADDRESS NUMBERS ON CONTRASTING BACKGROUND.
- 15. MENUBOARD, ILLUMINATED FROM FIXTURES
- ABOVE.
- 16. METAL CANOPY.
- 17. METAL CLAD WATERFALL WALL. COORDINATE WITH METAL CANOPY ABOVE AND FINISH TO MATCH. MAKE WATER TIGHT.
- PARAPET CORNICE ABOVE WOOD PLANK FINISH TO HAVE RECESSED LED STRIP LIGHTING.
- 19. BACKSIDE OF TOWER BEYOND TO BE FINISHED TO MATCH FRONT FACE AND SIDES.
- DRIVE-THRU CANOPY.
- 21. QUARTZ COUNTERTOP TO EXTEND THROUGH WALL OPENING AT ROLL-UP DOOR.

EXTERIOR FINISH SCHEDULE

MARK	MATERIAL (NO ALTERNATIVES ALLOWED)
A	CONCRETE LOOK WALL PANELS ON TOWERS KOL PANELS - COLOR: TELEGREY - FINISH: SMOOTH
В	VERTICAL WOOD PLANKS (ENGINEERED) NEW TECHWOOD, ULTRASHIELD NATURALE, COMPOSITE SIDING TONGUE & GROOVE US09, 5-9/16" X 1/2", COLOR: PERUVIAN TEAK (TK) USE COMPLETE SYSTEM COMPONENTS AND TRIMS.
C	DRYVIT E.I.F.S. STUCCO SYSTEM W/ SANDBLAST TEXTURE SANDBLAST NTX 108ST MANOR WHITE BATCH #7264-QT - PASTEL BASE STRATATONE
D	METAL DOORS & FRAMES, PAINT TO MATCH 'C' ABOVE
E	ATAS POWDERCOATED METAL PARAPET CORNICE, WALL CAP, DRIVE-THRU CANOPY FASCIA. PAINT LOUVER STRAP TO MATCH. COLOR: CLASSIC BRONZE
F	METAL CANOPY W/ PAINT FINISH TO MATCH 'E' ABOVE
G	METAL LOUVERS W/ KOROSEAL, REALTEC ARCHITECTURAL FILM. COLOR: TEC-5070 WALNUT SG, CUSTOM SIZE CONTACT: MICHAEL FOCKLER - KOROSEAL #480.753.5474; MFOCKLER@KOROSEAL.COM
H	METAL PARAPET CAP AT TOWER. COLOR TO MATCH 'A'
J	OLDCASTLE SUPERLITE, SPLIT FACE C.M.U 4" X 8" X 16" SERIES: ECHELON - COLOR: OPAL

NOTES:

1. E.I.F.S. SYSTEM TO BE DRYVIT OUTSULATION SYSTEM OR EQUAL, INSTALLED PER ICC-ESR

2. MANUFACTURER'S PRODUCT INSTALLATION SPECIFICATIONS SHALL BE MADE AVAILABLE TO FIELD INSPECTOR UPON REQUEST.

DRAWN BY: DATE: 06.10.2024 23-267 # DATE: DESCRIPTION:

AS NOTED

SCALE:

1.0

PRIME GRILL STORE NO. 11124

9 PRIME

WEST GUADALUPE ROAD A, ARIZONA 85021






A6.0

DRB

NORTH E	LEVATION - 695 SQ. FT.			
SYMBOL	MATERIAL	SQ. FT.	PERCENT	
A	CONCRETE	291	41.9%	
В	VERTICAL WOOD PLANK	160	23.0%	
С	STUCCO	113	15.3%	
E/F	METAL CANOPIES & FLASHING	58	8.3%	
J	SPLIT-FACED CMU WAINSCOT	73	10.5%	



EAST ELI	/ATION - 1,449.5 SQ. FT.		
SYMBOL	MATERIAL	SQ. FT.	PERCENT
	CONCRETE	322.5	22.2%
В	VERTICAL WOOD PLANK	262.0	18.0%
С	STUCCO	373.5	25.8%
E/F	METAL CANOPIES & FLASHING	144.5	10.0%
J	SPLIT-FACED CMU WAINSCOT	131.0	9.0%
	STOREFRONT & WALK-IN DOOR	216.0	15.0%


+10'-0" A.F.F.

B.O. FRONT CANOPY /
T.O. STOREFRONT

+0'-0"
FINISH FLOOR

O'-6"
T.O. ASPHALT

16



EAST ELEVATION - ENTRANCE SIDENOR

SCALE: 1/4"=1'-0"

+0'-0" FINISH FLOOR -0'-6" T.O. ASPHALT

622/12/5/11

D

SCALE: 1/4"=1'-0"

+23'-0" A.F.F.

T.O. LOW REAR TOWER

+20'-0" A.F.F. T.O. LOW PARAPET

+/-14'-6" A.F.F.
T.O. ROOF / LOW SIDE

+8'-0" A.F.F. B.O. REAR CANOPY

- FIRE RISER ROOM DOOR TO HAVE SIGNAGE AS
- EXTERIOR RATED WALK-IN COOLER PANEL & DOOR
- DELIVERY DOOR BELL BUTTON AT +48" A.F.F. AT REAR SERVICE DOOR.
- INTO TOWER WALL ABOVE DRIVE-THRU WINDOW. REFER TO MECHANICAL DRAWINGS.
- DASHED LINE INDICATES OUTLINE OF ROOFTOP
- 11. EXTERIOR LIGHTING, REFER TO ELECTRICAL
- 12. HOSE BIBB, REFER TO PLUMBING DRAWINGS.
- 13. BOLLARD W/ 2" REFLECTIVE YELLOW TAPE AT TOP
- 14. 12" TALL BLACK HELVETICA BUILDING ADDRESS
- 15. MENUBOARD, ILLUMINATED FROM FIXTURES
- 17. METAL CLAD WATERFALL WALL. COORDINATE WITH METAL CANOPY ABOVE AND FINISH TO MATCH. MAKE
- 18. PARAPET CORNICE ABOVE WOOD PLANK FINISH TO
- 19. BACKSIDE OF TOWER BEYOND TO BE FINISHED TO
- 21. QUARTZ COUNTERTOP TO EXTEND THROUGH WALL

KEYED NOTES

SCALE:

DRAWN BY: DATE:

PROJECT NUMBER:

DATE: DESCRIPTION:

PRIME GRILL

AS NOTED

06.10.2024

23-267

S.E.S. CLOSET DOORS TO HAVE SIGNAGE AS REQUIRED BY THE ELECTRIC SERVICE.

REQUIRED BY THE FIRE DEPARTMENT.

3. SPEAKER ORDER STAND W/ CREDIT CARD READER AND WEATHER SHIELD.

WITH BLACK FACTORY FINISH.

EXTERIOR WALL MOUNTED AIR CURTAIN, RECESSED INTO METAL CANOPY. REFER TO MECHANICAL

EXTERIOR WALL MOUNTED AIR CURTAIN, RECESSED

8. DRIVE-THRU WINDOW RECESSED INTO TOWER, SILL TO BE CLAD WITH 16 GA. S/S WITH 2" EDGE TURN DOWN.

EQUIPMENT.

10. LINE OF ROOF DECK, SHOWN DASHED.

NUMBERS ON CONTRASTING BACKGROUND.

ABOVE.

METAL CANOPY.

WATER TIGHT.

HAVE RECESSED LED STRIP LIGHTING.

MATCH FRONT FACE AND SIDES.

DRIVE-THRU CANOPY.

OPENING AT ROLL-UP DOOR.

22. ROOF DRAIN OUTLETS. ROOF DRAINS TO BE ONCEALED IN EXTERIOR WALL CONSTRUCTION.

EXTERIOR FINISH SCHEDULE

MARK	MATERIAL (NO ALTERNATIVES ALLOWED)
A	CONCRETE LOOK WALL PANELS ON TOWERS KOL PANELS - COLOR: TELEGREY - FINISH: SMOOTH
В	VERTICAL WOOD PLANKS (ENGINEERED) NEW TECHWOOD, ULTRASHIELD NATURALE, COMPOSITE SIDING TONGUE & GROOVE US09, 5-9/16" X 1/2", COLOR: PERUVIAN TEAK (TK) USE COMPLETE SYSTEM COMPONENTS AND TRIMS.
С	DRYVIT E.I.F.S. STUCCO SYSTEM W/ SANDBLAST TEXTURE SANDBLAST NTX 108ST MANOR WHITE BATCH #7264-QT - PASTEL BASE STRATATONE
D	METAL DOORS & FRAMES, PAINT TO MATCH 'C' ABOVE
E	ATAS POWDERCOATED METAL PARAPET CORNICE, WALL CAP, DRIVE-THRU CANOPY FASCIA. PAINT LOUVER STRAP TO MATCH. COLOR: CLASSIC BRONZE
F	METAL CANOPY W/ PAINT FINISH TO MATCH 'E' ABOVE
G	METAL LOUVERS W/ KOROSEAL, REALTEC ARCHITECTURAL FILM. COLOR: TEC-5070 WALNUT SG, CUSTOM SIZE CONTACT: MICHAEL FOCKLER - KOROSEAL #480.753.5474; MFOCKLER@KOROSEAL.COM
H	METAL PARAPET CAP AT TOWER. COLOR TO MATCH 'A'
J	OLDCASTLE SUPERLITE, SPLIT FACE C.M.U 4" X 8" X 16" SERIES: ECHELON - COLOR: OPAL
NOTES: 1. E.I.F.S. SYSTI	EM TO BE DRYVIT OUTSULATION SYSTEM OR EQUAL, INSTALLED PER ICC-ESR

FIELD INSPECTOR UPON REQUEST.

NOTES:

1. E.I.F.S. SYSTEM TO BE DRYVIT OUTSULATION SYSTEM OR EQUAL, INSTALLED PER ICC-ESR 2. MANUFACTURER'S PRODUCT INSTALLATION SPECIFICATIONS SHALL BE MADE AVAILABLE TO

DRB

A6.1



WEST ELEVATION			
YMBOL	MATERIAL	SQ. FT.	PERCENT
Α	CONCRETE	263	18.4%
В	VERTICAL WOOD PLANK	143	10.0%
С	STUCCO or DOORS	391	27.4%
E/F	METAL CANOPIES & FLASHING	169	11.8%
G	LOUVERS	245	17.2%
J	SPLIT-FACED CMU WAINSCOT	212	14.9%





- S.E.S. CLOSET DOORS TO HAVE SIGNAGE AS REQUIRED BY THE ELECTRIC SERVICE.
- FIRE RISER ROOM DOOR TO HAVE SIGNAGE AS REQUIRED BY THE FIRE DEPARTMENT.

AND WEATHER SHIELD.

- SPEAKER ORDER STAND W/ CREDIT CARD READER
- EXTERIOR RATED WALK-IN COOLER PANEL & DOOR
- WITH BLACK FACTORY FINISH.
- DELIVERY DOOR BELL BUTTON AT +48" A.F.F. AT REAR SERVICE DOOR.
- EXTERIOR WALL MOUNTED AIR CURTAIN, RECESSED INTO METAL CANOPY. REFER TO MECHANICAL
- EXTERIOR WALL MOUNTED AIR CURTAIN, RECESSED INTO TOWER WALL ABOVE DRIVE-THRU WINDOW. REFER TO MECHANICAL DRAWINGS.
- DRIVE-THRU WINDOW RECESSED INTO TOWER, SILL TO BE CLAD WITH 16 GA. S/S WITH 2" EDGE TURN DOWN.
- DASHED LINE INDICATES OUTLINE OF ROOFTOP
- 10. LINE OF ROOF DECK, SHOWN DASHED.
- 11. EXTERIOR LIGHTING, REFER TO ELECTRICAL DRAWINGS.
- 12. HOSE BIBB, REFER TO PLUMBING DRAWINGS.
- 13. BOLLARD W/ 2" REFLECTIVE YELLOW TAPE AT TOP
- 14. 12" TALL BLACK HELVETICA BUILDING ADDRESS NUMBERS ON CONTRASTING BACKGROUND.
- 15. MENUBOARD, ILLUMINATED FROM FIXTURES ABOVE.
- METAL CANOPY.
- 17. METAL CLAD WATERFALL WALL. COORDINATE WITH METAL CANOPY ABOVE AND FINISH TO MATCH. MAKE WATER TIGHT.
- 18. PARAPET CORNICE ABOVE WOOD PLANK FINISH TO HAVE RECESSED LED STRIP LIGHTING.
- 19. BACKSIDE OF TOWER BEYOND TO BE FINISHED TO MATCH FRONT FACE AND SIDES.
- 20. DRIVE-THRU CANOPY.
- 21. QUARTZ COUNTERTOP TO EXTEND THROUGH WALL OPENING AT ROLL-UP DOOR.

DATE: DESCRIPTION:

PROJECT NUMBER:

AS NOTED

06.10.2024

23-267

REC

SCALE:

DRAWN BY:

PRIME **GRILL**

STORE NO. 11124

ROAD PRIMI



02

2

90

UBMIT

DRB



VERTICAL WOOD PLANKS (ENGINEERED) NEW TECHWOOD, ULTRASHIELD NATURALE, COMPOSITE SIDING TONGUE & GROOVE US09, 5-9/16" X 1/2", COLOR: PERUVIAN TEAK (TK) USE COMPLETE SYSTEM COMPONENTS AND TRIMS. DRYVIT E.I.F.S. STUCCO SYSTEM W/ SANDBLAST TEXTURE SANDBLAST NTX 108ST MANOR WHITE BATCH #7264-QT - PASTEL BASE | STRATATONE METAL DOORS & FRAMES, PAINT TO MATCH 'C' ABOVE ATAS POWDERCOATED METAL PARAPET CORNICE, WALL CAP, DRIVE-THRU CANOPY FASCIA. PAINT LOUVER STRAP TO MATCH. COLOR: CLASSIC BRONZE

EXTERIOR FINISH SCHEDULE

MATERIAL (NO ALTERNATIVES ALLOWED)

CONCRETE LOOK WALL PANELS ON TOWERS KOL PANELS - COLOR: TELEGREY - FINISH: SMOOTH

METAL CANOPY W/ PAINT FINISH TO MATCH 'E' ABOVE METAL LOUVERS W/ KOROSEAL, REALTEC ARCHITECTURAL FILM.


COLOR: TEC-5070 WALNUT SG, CUSTOM SIZE CONTACT: MICHAEL FOCKLER - KOROSEAL #480.753.5474; MFOCKLER@KOROSEAL.COM METAL PARAPET CAP AT TOWER. COLOR TO MATCH 'A'

OLDCASTLE SUPERLITE, SPLIT FACE C.M.U. - 4" X 8" X 16" SERIES: ECHELON - COLOR: OPAL

NOTES:

1. E.I.F.S. SYSTEM TO BE DRYVIT OUTSULATION SYSTEM OR EQUAL, INSTALLED PER ICC-ESR

2. MANUFACTURER'S PRODUCT INSTALLATION SPECIFICATIONS SHALL BE MADE AVAILABLE TO









ANGIE'S PRIME GRILL EXTERIOR RENDERING

MESA | JULY 2024 | 2





ANGIE'S PRIME GRILL EXTERIOR RENDERING

MESA JULY 2024