











<u>EVERGREEN TREES</u>	<u>QTY</u>	<u>BOTANICAL / COMMON NAME</u>	<u>SPEC</u>
	7	Acacia pendula / Weeping Myall	24"box
	2	Acacia pendula / Weeping Myall	36"box
	8	Acacia salicina / Willow Acacia	24"box
<u>SHRUBS</u>	<u>QTY</u>	<u>BOTANICAL / COMMON NAME</u>	<u>SPEC</u>
	13	Acacia redolens 'Low Boy' / Low Boy Bank Catclaw	5 gal
	22	Agave angustifolia 'Marginata' / Variegated Caribbean Century Plant	1 gal
	16	Chrysactinia mexicana / Damianita	1 gal
	30	Dalea frutescens / Black Dalea	5 gal
	32	Hesperaloe parviflora 'Surprise Bouquet' / Surprise Bouquet Red Yucca	1 gal

	Quantity	Required	Provided
Parking Landscape			
<i>Landscape Islands</i>			
<i>total islands</i>	16		
<i>1 shade tree / island</i>		16	16
<i>3 shrubs / island</i>		48	52
<i>Divider Medians</i>			
<i>total parking spaces</i>	61		
<i>1 shade tree / 8 parking spaces</i>		7.63	17
<i>6 shrubs / 8 parking spaces</i>		45.75	61
Plant Size			
<i>total trees</i>	17		
<i>min 10% of req trees are 36"box</i>		1.70	2
<i>remainder of req trees are min 24"box</i>		Y	Y

GENERAL LANDSCAPE NOTES

1. The Contractor shall verify and coordinate all final grades with the Landscape Architect and or design team prior to completion.
2. Location and placement of all plant material shall be coordinated with the Landscape Architect prior to installation.
3. Location of all utilities are approximate, the Contractor shall field verify locations prior to commencement of construction operations.
4. Refer to Civil Drawings for all grading and berming, erosion control, storm drainage, utilities and site layout.
5. Plant quantities are for information only, drawing shall prevail if conflict occurs. Contractor is responsible for calculating own quantities and bid accordingly.
6. Tree locations in areas adjacent to drives, walks, walls and light fixtures may be field adjusted as approved by Landscape Architect.
7. The Contractor shall report subsurface soil or drainage problems to the Landscape Architect.
8. The plan is subject to changes based on plant size and material availability. All changes or substitutions must be approved by the City of Mesa, Arizona and the Landscape Architect.
9. Aluminum landscape edging to be used on all landscape beds adjoining turf areas as noted on landscape plans.
10. Landscape Contractor shall be responsible for watering all plant material until the time that a permanent water source is ready.
11. The Contractor shall show proof of procurement, sources, quantities, and varieties for all shrubs, perennials, ornamental grasses, and annuals within 21 days following the award of the contract.
12. Contractor shall provide full maintenance for newly landscaped areas for a period of 30 days after the date of final acceptance. At the end of the maintenance period, a healthy, well-rooted, even-colored, viable turf and landscaped area must be established. The landscaped areas shall be free of weeds, open joints, bare areas, and surface irregularities.