

VICINITY MAP
NTS





APN# 139-49-027D
EX. ZONING: LI
EX. USE: GAS STATION

OVERALL SITE PLAN

OLD MESA DRIVE: OLD MESA DRIVE WILL BE ACQUIRED BY THE PROPERTY OWNER AND REMOVED FROM CITY OWNERSHIP. THERE ARE TWO OPTIONS BEING CONSIDERED REGARDING THE ULTIMATE OWNERSHIP.

1. THE FIRST OPTION AND MORE LIKELY SCENARIO WILL ADD THE WEST HALF OF THE OLD MESA DR. ROW TO THE PROJECT SITE AND IT WILL BE LANDSCAPED TO MEET CITY CODE.
2. THE SECOND OPTION WILL EXPLORE THE POTENTIAL INTEREST OF THE NEIGHBORING PROPERTY OWNERS TO THE EAST TO ACQUIRE THIS WEST HALF OF THE ROW.

THIS ISSUE WILL BE RESOLVED PRIOR TO THE DESIGN REVIEW BOARD PRESENTATION.



APN# 139-49-028A
EX. ZONING: LI
EX. USE: USED CAR SALES

SITE DATA

Hotel Site Area (128,234sf) 2.9 Ac.

PARCEL

139-49-027C (Portion of 5.7 Ac)

ZONING

Existing - Light Industrial (LI)

Building Information

4 Floors , 122 Keys, Total Bldg SF = 46,158
Building Const.Type: 5A Occupancy R-1
Automatic Fire Sprinkler System - NFPA 13

DEVELOPMENT STANDARDS

Perimeter Building & Parking Setbacks	
Baseline Road	15'
Mesa Drive	15'
East - Side Yard	0'
North - Rear Yard (interior lot line)	0'

Building Height

Max. Height of sloped roof at Stair Tower	45'-0"
Primary Parapet	39'-6"
Secondary Parapet	40'-8"
Entry Feature	44'-9 1/2"

Lot Coverage (13,111sf under roof / 3.0 Ac) 10.2%

Parking

Required: 1 sp/unit: 122	122
ADA Spaces: 6 included	

Parking Required 122

Parking Provided 131

OPEN SPACE CALCULATION
TOTAL BLDG.AREA.: 46,158 S.F.
OPEN SPACE REQUIRED/ 1% OF BLDG.: 462 S.F.
OPEN SPACE PROVIDED: ±465 S.F.

PROPOSED WOODSPRING SUITES HOTEL

1911 S. MESA DRIVE, MESA, AZ

PREPARED FOR: B.G. EDGE LLC

PRELIMINARY SITE PLAN

THIS DRAWING IS AN INSTRUMENT OF SERVICE AND THE PROPERTY OF GILMORE PLANNING & LANDSCAPE ARCHITECTURE. THIS DRAWING MAY NOT BE REPRODUCED OR ANY REPRODUCTION HEREOF USED, WITHOUT THEIR WRITTEN PERMISSION. © COPYRIGHT 2020

SCALE: 1" = 20'
DATE: 10.19.20
GPLA JOB# 20017

