


DESIGN REVIEW BOARD




DRB20-00563

Location

 South of Ray Road on the east side of Power Road





Request

Design Review

Purpose

Development of a hotel


Street View



Looking west into the site from the commercial center

Site Plan

- Access through the group commercial center from Power Road
- Secondary access to the north



Landscape Plan

FOUNDATION BASE DATA

AVERAGE OF TOTAL DISTANCE FROM BUILDING TO FACE OF CURB

WEST (FUBLIC ENTRANCE SIDE)

NORTH

EAST

SOUTH

15 LF

EAST

SOUTH

15 LF

OPEN SPACE LIVE PLANT COVERAGE

QUIRED OPEN SPACE	232 S.F
OVIDED OPEN SPACE	914 S.F
E PLANT COVERAGE	510 S.F
(I) SHADE TREE	

(1) SHADE TREE
 (1) COLUMNAR EVERGREEN TREE
 (13) MEDIUM SHRUB
 (11) SMALL SHRUB

(II) SMALL SHRUB
REQUIRED LIVE PLANT COVERAGE
PROVIDED LIVE PLANT COVERAGE

LANDSCAPE DATA

GROSS SITE AREA	105,469 S.F
LANDSCAPE AREA	31,887 S.F
LANDSCAPE COVERAGE	30.9%

31,887 S.F

1,000 S.F

OPEN SPACE DATA


DAINDSCAFE AREA
DECORATIVE VEHICULAR PAVING AREA

PLANT LEGEND

SYMB		COMMON NAME	SIZE	QTY
TREES				
_	Acacia anuera	Mulga	24° Box	3
0	Acacia salicina	Willow Acacia	24° Box	15
\sim	Chitalpa tashkentensis 'Pink Dawn'	Chitalpa	24° Box	4
[/]	Pistacia 'Red Push'	Red Push Pistache	36* Box	18
\sim	Phoenix dactylifera	Date Palm 15' in heig	ht (15 Gal)	10
$(\downarrow\downarrow)$	Pinus eldarica	Mondel Pine	24" Box	17
4	Ulmus parvifolia	Chinese Evergreen Elm	36* Box	2
SHRU	BS/ACCENTS	COMMON NAME	SIZE	OTY
(1)	Agave americana	Century Plant	5 Gal	6
8	Agave desmettiana	Smooth Agave	5 Gal	21
Ä	Caesalpinia cacalaco "Smoothies"	Smooth Cascalote	5 Gal	9
Õ	Caesalpinia pulcherrima	Red Bird of Paradise	5 Gal	28
淼	Dasylirion quadrangularum	Mexican Grass Tree	5 Gal	28
80	Hesperaloe parviflora 'Brakelights'	Brakelights Red Yucca	5 Gal	35
٠	Justicia spicigera	Mexican Honeysuckle	5 Gal	59
	Leucophyllum candidum 'Thunder Cloud'	Thunder Cloud Sage	5 Gal	32
30**•⊕⊕®•	Leucophyllum langmaniae 'Rio Bravo'	Rio Bravo Sage	5 Gal	42
0	Muhlenbergia capillaris 'Regal Mist'	'Regal Mist' Muhly	5 Gal	78
0	Portulacaria afra minima	Dwarf Elephant Food	5 Gal	6
(i)	Ruellia peninsularis	Desert Ruella	5 Gal	21
0	Russelia equisetiformus	Coral Fountain	5 Gal	27
	Simmondsia chinensis "Vista"	Compact Jojoba	5 Gal	34
90	Tecoma x 'Orange Jubilee'	Orange Jubilee	5 Gal	48
4	Tecoma stans 'Gold Star'	Yellow Bells	5 Gal	25
GROL	INDCOVERS	COMMON NAME	SIZE	QTY
(4)	Eremophila prostrata 'Outback Sunrise'	"Outback Sunrise"	l Gal	24
	Lantana x 'Dullas Red'	Dallas Red Lantana	I Gal	49
Θ	Lantana x 'New Gold'	New Gold Lantana	I Gal	63
VINE		COMMON NAME	SIZE	QTY
_	Bougainvillea species	Bougainvillea Vine	5 Gal	10
MATE	RIAL			
	Decomposed Granite "Santa Fe Gold"			31,887 S.F.
	Decorative Vehicular Paving Stamped Concrete, Pattern: Ashlar Slate	s, Color: Taupe		1,000 S.F.
12000	Brooked Connects Brooks			244455

CITY OF MESA PLANT DATA

PROPERTY PERIMETER (1,314 L.F.)	REQUIRED	PROVIDED
3 NON DECIDUOUS TREES AND 20	40 TREES	40 TREES
SHRUBS PER 100 L.F. OF ADJACENT	263 SHRUBS	263 SHRUBS
PROPERTY LINE		
FOUNDATION BASE (688 L.F.)	REQUIRED	PROVIDED
I TREE PER 50 L.F. OF EXTERIOR	14 TREES	14 TREES
BUILDING WALL		
10% OF FOUNDATION BASE	2 TREES	2 TREES
TREES TO BE 36" BOX SIZE TREES		
TREE SIZE	REQUIRED	PROVIDED
36" BOX (25% MIN.)	18 TREES	20 TREES
24" BOX (50% MIN.)	35 TREES	35 TREES



West Elevation



West Elevation

 STONE =
 2,521.41 = 24%

 FIBER CEMENT BOARD =
 3,955.88 = 38%

 STUCCO =
 2,347.49 = 23%

 WINDOWS/HVAC =
 1,550.00 = 15%

 TOTAL =
 10,374.78

PER MZO 11-6-3 B2, NO MORE THAN 50% OF THE TOTAL FACADE IS COVERED BY ONE MATERIAL

East Elevation



East Elevation

 STONE =
 2,769.73 = 29%

 FIBER CEMENT BOARD =
 3,940.82 = 42%

 STUCCO =
 1,327.41 = 14%

 WINDOWS/HVAC =
 1,374.09 = 15%

 TOTAL =
 9,412.05

PER MZO 11-6-3 B2, NO MORE THAN 50% OF THE TOTAL FACADE IS COVERED BY ONE MATERIAL

North and South Elevations



North Elevation

TOTAL	0 470 50	
ROOF =	130.83	= 4%
WINDOWS/HVAC =	148.82	= 5%
STUCCO =	1,261.63	= 40%
FIBER CEMENT BOARD	= 769.72	= 24%
STONE =	865.52	= 27%

PER MZO 11-6-3 B2, NO MORE THAN 50% OF THE TOTAL FACADE IS COVERED BY ONE MATERIAL



South Elevation

STONE =		945.89	=	34
FIBER CEMENT BOARD	=	900.43		
STUCCO =		807.60	= ;	28
WINDOWS/HVAC =		59.02	=	2
ROOF =		51.29	=	2
TOTAL -	- 9	764 22		

PER MZO 11-6-3 B2, NO MORE THAN 50% OF THE TOTAL FACADE IS COVERED BY ONE MATERIAL

Rendering




Color and Material Board






Lighting



Lighting



CACTUS GROVE PROPERTIES ILC (AGRICULTURE/VACANT LAND)


STATISTICS					
DESCRIPTION	AVG (R)	MAX	MN (%)	MAXIMN	AVC/MN
PORTE COCHERE	7.1	9.1	4.2	2.2:1	1.7:1
COVERED PARKING	3.0	5.0	1.5	3.3.1	2.0:1
POOL AREA	2.6	4.9	1.4	3.5:1	1.9:1
SITE AREA	1.4	9.1	0.0	NA	NA

GENERAL NOTES:

EXTERIOR LIGHTING IS DESIGNED FOR DUSK TO DAWN OPERATION
VIA PHOTOCOLL ON, TWELLOCK OFF, FOR THE SWETTY OF
GUESTS AND DUE TO THE HOTEL OPERATING 24/7, AN AFTER
HOURS REDUCTION IN LIGHT LEVELS IS NOT REQUIRED.

WORK NOTES:

- NOT USED.
 SIX FOOT FENCE ALONG PROPERTY LINE.
- 3. COVERED PARKING AREA.
- MONUMENT SIGN: COORDINATE LIGHTING WITH MANUFACTURER OR VENDOR PRIOR TO ROUGH—IN.
- 5. PROVIDE FLOOD LIGHT FIXTURE 'SOA' IF FLAG POLE IS PRESENT. FIXTURES ARE MOUNTED ON TRELLIS. REFER TO ARCHITECTURAL DRAWNOS FOR ELEVATION DETAILS.





Design Guidelines

Section 11-6-3

- ✓ Design incorporates multiple materials
- ✓ Wall articulation
- ✓ Roof articulation
- No more than fifty percent (50%) of the total façade may be covered with one (1) single material

Summary

Findings

- ✓ Staff has no major concerns
- ✓ Project meets MZO requirements
- ✓ Staff welcomes any feedback



DESIGN REVIEW BOARD